

35-23-1E

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- L. W. PRUNTY
Farm- Sadowsky No. 1

SEC. 35 T. 23 R. 1E
SE SW SE

Total Depth. 3661'
Comm. 10-30-56 Comp. 11-14-56
Shot or Treated.
Contractor. Fees Drilling Company
Issued. 12-15-56

County Harvey KANSAS



Elevation. 1485' RB

CASING:

8 1/4" @210' w/125 sx cem.

Production. Dry

Figures indicate Bottom of Formations.

Depths were measured from the top of the Kelly Bushing which was 1 foot above the rig floor.

clay sandy	10
sand	25
shale w/lime strks	150
shale	207
Anhydrite	210
shale w/lime strks	355
lime strks	400
shale w/lime strks	870
lime	890
shale w/lime strks	975
shale	1010
shale w/lime strks	1862
lime	1870
shale w/lime strks	1987
shale	2343
lime	2475
shale	2485
lime	2760
lime shaly	2780
lime	2824
shale w/lime strks	2965
shale w/sand	3024
sand	3042
shale & sand	3046
lime	3103
lime & chert	3143
lime	3174
lime & chert	3204
lime	3286
shale	3405
shale & lime	3430
chert & dolomite	3470
shale	3525
shale & lime	3601
dolomite & chert	3661
Total Depth	

NO ELECTRIC LOG RUN

TOPS	
Lansing Lime	2343
Kansas City	2535

Base/Kansas City	2729
Pennsylvanian	
Conglomerate	2955
Burgess Sand	3024
Mississippi Lime	3042
Base/Mississippi lime)	
Kinderhook shale	3301
Hunton	3401
Maquoketa shale	3467
Viola	3499
Simpson	3520
Arbuckle	3601