

ORIGINAL

RECEIVED GEOLOGICAL REPORT

JAN 25 2002

KCC WICHITA

Viva International, Inc.

#23 Pearson

**1677fS/4220fE Sec 22-T23S-R10E
Greenwood County, Kansas**

COMMENCED:	8/1/01	STATUS:	Oil
COMPLETED:	8/8/01	A.P.I. NO:	15-073-23925
CONTRACTOR:	Rig Six Drilling Co.	OPER LIC:	5556
SIZE OF HOLE:	7 7/8	FIELD:	Burkett
SURFACE PIPE:	8 5/8 @ 200'	ELEVATION:	1316GL
CEMENTED:	135sx	LOGS RUN:	None
LONG STRING:	5½ @ 2250	MUD SYSTEM:	Chemical
CEMENTED:	250 sacks	OTHER:	
RTD:	2252		

Dean Seeber, Geologist

ORIGINAL

<u>Elevation</u>	<u>1316GL</u>
<u>Formation</u>	<u>Tops Datum</u>
Cherokee	1966 (-650)
Ardmore	2045 (-729)
Lower Bartlesville Sandstone	2162 (-846)
Base Bartlesville Sandstone	2209 (-893)
RTD	2252 (-936)

Major Zones of Interest

Lower Bartlesville 2162 - 2176

Sandstone, buff, fine-grained, micaceous, slightly shaley, good porosity, good fluorescence and show of free oil.

2176 - 2178

Sandy, limestone.

2178 - 2190

Sandstone, as above, shaley, good shows.


2190 - 2209

Sandstone, as above, cleaner, slightly coarser.

Summary

Due to the good sand development in the Lower Bartlesville, 5½" casing was run to TD and cemented for completion.

Yours sincerely,



Dean E. Seeber
Petroleum Geologist

