

RECEIVED

JAN 25 2002 GEOLOGICAL REPORT
KCC WICHITA

Viva International, Inc.

#24 Pearson

1140fS/1832fW Sec 22-T23S-R10E
Greenwood County, Kansas

COMMENCED:	8/13/01	STATUS:	Oil
COMPLETED:	8/18/01	A.P.I. NO:	15-073-23926
CONTRACTOR:	Rig Six Drilling Co.	OPER LIC:	5556
SIZE OF HOLE:	7 7/8	FIELD:	Burkett
SURFACE PIPE:	8 5/8 @ 200'	ELEVATION:	1372
CEMENTED:	135'	LOGS RUN:	None
LONG STRING:	5½	MUD SYSTEM:	Chemical
CEMENTED:	250 sacks	OTHER:	
RTD:	2325		

Dean Seeber, Geologist

ORIGINAL

<u>Elevation</u>	<u>1372GL</u>	
<u>Formation</u>	<u>Tops</u>	<u>Datum</u>
Cherokee	2018	(-646)
Ardmore	2098	(-726)
Bartlesville	2340	(-868)
Base Bartlesville	2268	(-896)
RTD	2325	(-953)

Major Zones of Interest

Bartlesville 2222 - 2240

Sandstone, grey, fine-grained, micaceous, very shaley, tight, no shows.

2240 - 2250

Sandstone, light buff, fine-grained, micaceous, shaley, good fluorescence, fair odor, fair show of free oil.


2250 - 2268

Sandstone, buff, fine-grained, micaceous, cleaner than above, good door, good fluorescence, fair to good show of free oil.

Summary

Due tot he fair development of Bartlesville sand with oil shows, 5½" casing was set to test for production.

Yours sincerely,



Dean E. Seeber
Petroleum Geologist

