

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **SINCLAIR OIL & GAS COMPANY**

SEC. 32 T. 23 R. 10E

FARM **Thrall Unit** NO. **S-8**

LOC. **SW NW NW NE**

360' fr NL & 2445' fr EL of NE/4

TOTAL DEPTH **1388**

COUNTY **Greenwood**

COMM. **12-20-49**


COMP. **1-27-50**

SHOT OR TREATED

CONTRACTOR **Ward A. McGinnis**

ISSUED **12-23-50**

KANSAS



CASING

10 3/4" 102' cem. w/50 sx
 7" 1306' cem. w/75 sx
 4 1/2" 1339' (Tubing)

ELEVATION

PRODUCTION **Bailed 60 bbls.
 -2 hr. test**

FIGURES INDICATE BOTTOM OF FORMATIONS

All measurements are from surface level

soil	3
lime & shells	60
shale & shells	95
shale	102
shale & lime	823
lime	851
shale	919
lime shells & shale	944
shale & lime	1092
shale	1126
shale & shells	1169
lime shells & shale	1248
sand (Upper Sec. Douglas)	1295
shale	1304
sand (Lower Sec. Douglas), RTD	1339
shale blue	1349
lime gray	1354
shale blue	1356
lime gray	1360
lime white	1388
Total depth	

Tops:	Top	Bottom
Upper Douglas	1248	1295
Lower Douglas	1304	1339

Remarks:

Perf. at 1305'. Well bailed 60 barrels in two hrs, and fluid level lowered 160 feet. - from 500 feet to 340 feet from bottom.
 Upper section Douglas wtr sand 1248 to 1295. Lower section 1304 to 1339.