

Pg. 1

Arnold E. Kraft Oil Company
Gridley, Ks

Wiley Lease well #7

Skyy Drilling (contractor)

September 20, 2006

NE/NE Sec 14- T 23- R14E
990 FNL, 930 FEL
Elevation 1095

Measurements are 6 ft. above ground level.

1280-1290	Squirrel section no free oil, no flo, no odor
1290-1300	Sandy shale, little sand, no oil, no flo squirrel section
1440-1445	Gray shale
1445-1455	Gray shale, no Bartlesville, no oil, no flo
1510-1520	Gray shale
1520-1530	Gray shale, and scattered shells
1530-1540	Gray shale and coal streaks
1540-1550	Black shale
1550-1560	connection, black shale
1560-1570	Gray shale
1570-1575	Black shale
1575-1580	Light sandy shale
1580-1585	connection, sandy shale, dark
1585-1590	Black shale, some sandy shale
1590-1595	Gray shale, light shale
1595-1600	Gray shady shale
1600-1605	Black shale
1605-1610	2 1/2 min., shale & soft lime
1611	3 min.
1612	3 1/2 min.
1613	4 1/2 min.
1614	3 min.
1615	2 1/2 min. Circ light brown lime to clear lime, no odor, no FLO, no oil

RECEIVED
DEC 15 2006
KCC WICHITA

Arnold E. Kraft Oil Company
Gridley, Ks

Wiley Lease well #7

Sky Drilling (contractor)

September 20, 2006

NE/NE Sec 14- T 23- R14E
990 FNL, 930 FEL
Elevation 1095

Measurements are 6 ft. above ground level.

1615	Burgess sand, clear no oil no Flo (10 min) 20 min. light lime & some chert no oil
1616	Top Miss
1617	1 1/2 min.
1618	1 min.
1619	1 min. cir 10 min. no odor, no FLO, no free oil. lime-sand cologomerde:lite lime & chert, no oil
1620	1 min.
1621	45 sec
1622	45 sec
1623	45 sec, connection, cir 10 min. slight odor- light brown, some oil, sight FLO
1624	45 sec
1625	45 sec
1626	1 min.
1627	1 min.
1628	45 sec lite lime, some chert, no oil, no FLO
1629	45 sec
1630	1 min.
1631	1 min.
1632	1 min.
1633	1 min.
1634	1 min.
1635	1 min.
1636	1 min.

RECEIVED
DEC 15 2006
KCC WICHITA

Arnold E. Kraft Oil Company
Gridley, Ks

Wiley Lease well #7

Skyy Drilling (contractor)

September 20, 2006

NE/NE Sec 14- T 23- R14E
990 FNL, 930 FEL
Elevation 1095

Measurements are 6 ft. above ground level.

1637	1 min.
1638	1 min.
1639	45 sec circ light brown no oil; 10 min. good odor, show oil some FLO, well developed dolomite. Perosity 20 min sandy dolomite, good odor, good FLO, no free oil
1640	45 sec
1641	1 min.
1642	1 1/2 min.
1643	2 min. circ 10 min. very light dolomite, good odor, slight FLO, 20 min. slight odor, light brown dolomite
1644	1 1/2 min.
1645	2 min.
1646	2 min.
1647	2 1/2 min.
1648	2 min.
1649	1 min.
1650	1 min.
1651	45 sec. circ 10 min. no FLO, light brown dolomite, no oil, slight odor 20 min. light brown dolomite, no oil, no FLO
1652	30 sec
1653	30 sec
1654	30 sec
1655	30 sec. Kelly down, circ 10 min. light light brown sand no FLO, no perosity, no oil.

RECEIVED
DEC 15 2006
KCC WICHITA

Arnold E. Kraft Oil Company
Gridley, Ks

Wiley Lease well #7

Skyy Drilling (contractor)

September 20, 2006

NE/NE Sec 14- T 23- R14E
990 FNL, 930 FEL
Elevation 1095

Measurements are 6 ft. above ground level.

1655

20 min. circ light lime & chert, no oil, no odor, no FLO
TD Plugged well

RECEIVED
DEC 15 2006
KCC WICHITA