

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

COPY

Form ACO-1
September 1999
Form Must Be Typed

WELL COMPLETION FORM
WELL HISTORY - DESCRIPTION OF WELL & LEASE

ku
men
7/22/08

Operator: License # 34047
Name: Ron-Bob Oil LLC
Address: PO Box 41
City/State/Zip: Neosho Falls, KS 66758
Purchaser: CMT Transportation, INC.
Operator Contact Person: Robert Christenson
Phone: (620) 365-0919
Contractor: Name: Nicholas L Brown
License: 32642

Wellsite Geologist: none
Designate Type of Completion:
 New Well Re-Entry Workover
 Oil SWD SIOW Temp. Abd.
 Gas ENHR SIGW
 Dry Other (Core, WSW, Expl., Cathodic, etc)

If Workover/Re-entry: Old Well Info as follows:
Operator: _____
Well Name: _____

Original Comp. Date: _____ Original Total Depth: _____
 Deepening Re-perf. Conv. to Enhr./SWD
 Plug Back _____ Plug Back Total Depth _____
 Commingled _____ Docket No. _____
 Dual Completion _____ Docket No. _____
 Other (SWD or Enhr.?) _____ Docket No. _____

5/20/2008 5/23/2008 5/23/2008
Spud Date or Date Reached TD Completion Date or
Recompletion Date Recompletion Date

API No. 15 - 207-27374-00-00
County: Woodson
____ NE ____ NW ____ NE Sec. 24 Twp. 23 S. R. 16 East West
4867 feet from S / N (circle one) Line of Section
1405 feet from E / W (circle one) Line of Section


Footages Calculated from Nearest Outside Section Corner:
(circle one) NE SE NW SW
Lease Name: Wolfe Well #: 18-B
Field Name: Neosho Falls-Leroy
Producing Formation: Squirrel
Elevation: Ground: 962' Kelly Bushing: none
Total Depth: 996' Plug Back Total Depth: none
Amount of Surface Pipe Set and Cemented at 40' Feet
Multiple Stage Cementing Collar Used? Yes No
If yes, show depth set _____ Feet
If Alternate II completion, cement circulated from 993
feet depth to surface w/ 110 sx cmt.

Drilling Fluid Management Plan
(Data must be collected from the Reserve Pit)
Chloride content fresh water ppm Fluid volume _____ bbls
Dewatering method used Evaporation
Location of fluid disposal if hauled offsite: _____
Operator Name: _____
Lease Name: _____ License No.: _____
Quarter _____ Sec. _____ Twp. _____ S. R. _____ East West
County: _____ Docket No.: _____

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: *Patricia J Schuster*
Title: Partner Date: July 24, 2008
Subscribed and sworn to before me this 8th day of July,
2008.
Notary Public: *Patricia J Schuster*
Date Commission Expires: December 31st 2009



KCC Office Use ONLY
 Letter of Confidentiality Received
 Wireline Log Received RECEIVED
 Geologist Report Received KANSAS CORPORATION COMMISSION
 UIC Distribution
JUL 11 2008

Operator Name: Ron-Bob Oil LLC Lease Name: Wolfe Well #: 18-B
 Sec. 24 Twp. 23 S. R. 16 East West County: Woodson

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <i>(Attach Additional Sheets)</i> Samples Sent to Geological Survey <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Cores Taken <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Electric Log Run <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <i>(Submit Copy)</i> List All E. Logs Run: Gamma Ray / Neutron	<input checked="" type="checkbox"/> Log Formation (Top), Depth and Datum <input type="checkbox"/> Sample Name squirrel Top Datum
--	---

CASING RECORD <input type="checkbox"/> New <input checked="" type="checkbox"/> Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
surface	12"	7"	17#	40'	Portland	10	
production	5 5/8"	2 7/8"	6.7#	993'	Quick Set	110	

ADDITIONAL CEMENTING / SQUEEZE RECORD				
Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
<input type="checkbox"/> Perforate				
<input type="checkbox"/> Protect Casing				
<input type="checkbox"/> Plug Back TD				
<input type="checkbox"/> Plug Off Zone				

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record <i>(Amount and Kind of Material Used)</i>	Depth
2	926' - 934 (17 shots)	75 gal 15% HCL, 4000# sand	

RECEIVED
 KANSAS CORPORATION COMMISSION
 JUL 11 2008
 CONSERVATION DIVISION
 WICHITA, KS

TUBING RECORD		Size	Set At	Packer At	Liner Run	<input type="checkbox"/> Yes <input type="checkbox"/> No	
Date of First, Resumerd Production, SWD or Enhr. 6/23/2008		Producing Method					
		<input type="checkbox"/> Flowing <input checked="" type="checkbox"/> Pumping <input type="checkbox"/> Gas Lift <input type="checkbox"/> Other (Explain)					
Estimated Production Per 24 Hours	Oil Bbls.	Gas Mcf	Water Bbls.	Gas-Oil Ratio	Gravity		
	.25						

Disposition of Gas Vented Sold Used on Lease Open Hole Perf. Dually Comp. Commingled _____
(If vented, Submit ACO-18.) Other (Specify) _____

NICHOLAS L. BROWN #32642
2481 110th
IOLA, KANSAS 66749

DRILL LOG
RON-BOB OIL LLC

Wolfe #18-B
API #15-207-27374-00-00
SEC. 24, T23S, R16E
WOODSON CO. KS

0-20	DIRT & CLAY
20-29	RIVER GRAVEL
29-84	SHALE
84-182	LIME
182-256	SHALE
256-270	LIME
270-278	SHALE
278-358	LIME
358-374	SHALE
374-386	LIME
386-410	SHALE
410-413	LIME
413-420	SHALE
420-482	LIME
482-488	BLACK SHALE
488-512	LIME
512-513	BLACK SHALE
513-536	LIME
536-670	SHALE
670-680	LIME
680-698	SHALE
698-704	BLACK SHALE
704-736	LIME
736-738	BLACK SHALE
738-752	LIME
752-800	SHALE
800-812	LIME
812-832	SHALE
832-835	BLACK SHALE
835-838	SHALE
838-878	LIME
878-882	BLACK SHALE
882-887	SHALE
887-890	BLACK SHALE
890-926	SHALE
926-934	SHALE W/OIL
934-996	SHALE

**5/20/2008 Drilled 12" hole and set
40' of 7" surface casing,
with 10 sx Portland Cement.**
5/21/2008 Started drilling 5 5/8" hole.
5/23/2008 Finished drilling to T.D. 996'

T.D. 996'

RECEIVED
KANSAS CORPORATION COMMISSION

JUL 11 2008

CONSERVATION DIVISION
WICHITA, KS