

CASING RECORD

LOCATION

Con SE NW SW

SEC 16T2 3R 11E.

Plotted Miller
Greenwood, MAR 26 1927

20" 10" 975
15 1-2 8 1-4 1550
12 1-2 550 6 5-8 1915
5 3-16

FARM D.A. Edwards
COMPANY The Texas Co. and Simmons.
CONTRACTOR
COMMENCED

NO. 1B COUNTY

COMPLETED

TOTAL DEPTH

SHOT

QUARTS BETWEEN

CORRESPONDENCE REGARDING THIS WELL SHOULD BE REFERRED TO The Texas Co.

Eldorado, Kansas.,

FIGURES INDICATE BOTTOM OF FORMATIONS.

REMARKS 3-26-27.

ELEVATION

INITIAL PRODUCTION 200bblx.



Formation	Depth	Formation	Depth.
soil brown soft	10	shale light soft	1525
lime white hard	30	lime white hard	1530
shale blue soft	80	shale white soft	1550
lime wh hard	130	lime brown hard	1560
shale blue soft	400	shale blue soft	1590
lime wh hard	440	shale light soft	1635
shale blue soft	530	lime white ha rd	1640
lime white hard	550	shale wh soft	1665
shale blue soft	600	lime brown hard	1670
lime white hard	620	shale blue soft	1770
shale dark soft	650	lime brown hard	1775
lime white hard	660	shale dark soft	1865
shale white soft	700	shale light soft	1875
lime white hard	720	shale dark soft	1880
shale blue soft	760	shale light soft	1915
lime white hard	790	sand grey soft	1978 Oil
shale white soft	800	shale dark soft	1981
lime white hard	805		
shale light soft	835		
sand light soft	970		
HFWlime light hard	985		
shale blue soft	1015		
lime white hard	1170		
shale light soft	1175		
lime brown hard	1185		
shale light soft	1240		
lime white hard	1305		
sand wh ha rd	1340		
lime brown hard	1345		
shale brown soft	1350		
lime brown hard	1380		
shale blue soft	1385		
lime white hard	1405		
shale blue soft	1425		
sand wh soft	1435		