


WELL LOG BUREAU, KANSAS GEOLOGICAL SOCIETY
UNION NATIONAL BANK BLDG., WICHITA, KANSAS

27365

CASING RECORD

LOCATION 330 S and 330 W. from the North and East line of the NW $\frac{1}{4}$ of SEC 16 T 23 R 11E. SW $\frac{1}{4}$

10" 1015 FARM D.A. Edwards NO. B3. COUNTY Greenwood.
8 1-4 1283? COMPANY The Texas Company.
15 1-2 6 5-8 1953 CONTRACTOR
12 1-26 01 5 3-16 COMMENCED 12-23-26 COMPLETED 1-11-27



TOTAL DEPTH SHOT QUARTS BETWEEN

CORRESPONDENCE REGARDING THIS WELL SHOULD BE REFERRED TO The Texas Co.

Wichita, Kansas.

ELEVATION

FIGURES INDICATE BOTTOM OF FORMATIONS.

INITIAL PRODUCTION 75 bbls.

REMARKS 2-5-27

Formation	Depth	Formation	Depth.
clay yellow soft	10	lime light hard	1310-
shale blue soft	20	shale light soft	1330
lime grey med	45	lime white hard	1385
shale blue soft	50	shale grey soft	1410
lime grey hard	65	lime white hard	1420
shale blue med	90	shale light soft	1430-
lime white hard	100	lime white hard	1450
shale light soft	150	lime white hard	1455
lime grey hard	160	shale light soft	1585
shale blue soft	165	Run 8 $\frac{1}{4}$ casing 1585	
lime light hard	170	lime white hard	1590
shale dark soft	225	shale light soft	1600
lime light hard	235	lime white hard	1610
shale dark soft	325	shale light soft	1625
lime light hard	330	lime white hard	1630
shale light soft	335	shale light soft	1670
lime light hard	370	lime grey hard	1675
shale blk soft	380	shale light soft	1715
lime light hard	395	lime white hard	1725
shale dark soft	415	shale dark soft	1953
lime light hard	435	Run 6-5/8 1953	
shale light soft	445	lime shell wh hard	1956
lime grey hard	450	oil sand dark soft	2011
shale light hard	455	S. L.M. T.D.	2011
lime lighthard	465		
shale grey soft	485		
lime light hard	497		
shale light soft	505		
lime grey hard	520		
shale light soft	535		
lime grey hard	545		
shale grey soft	565		
lime light hard	570		
shale blue soft	584		
lime grey hard	594		
shale light soft	605		
run 601 12 $\frac{1}{2}$ casing			
lime grey hard	615		
shale light soft	630		
lime grey hard	635		
shale light soft	640		
lime white hard	650		
shale light soft	655		
lime white hard	665		
lime white hard	715		
shale blue soft	875		
lime grey hard	880		
shale light soft	895		
sand water light soft	920		
HFV 895-920			
shale blue med	980		
lime white hard	995		
shale blue soft	1012		
lime white hard	1055		
run 10" pipe at 1015			
shale blue soft	1065		
lime white hard	1150		
shale dark soft	1290		

Note 6-5/8 Originally set at 1922
Later UR and set 1958