

L S Well Service
543-A 22000 Rd.
Cherryvale, KS 67335
620-328-4433

DRILLER LOG
Robert Christenson
C S OIL

CHRISTENSON # 10
API#207-26799-00-00
SEC. 33, T23, R17E
WOODSON CO, KS

3-23-03 Drilled 11 1/4" hole and set 46'
of 8 5/8" surface pipe and set with 30 sx.
of Portland cement.

3-24-03 Started drilling 6 3/4" hole

3-24-03 Finished drilling to T.D. 1240'

0-5'	DIRT
5-12'	RIVER ROCK
12-14'	LIME
14-20'	SHALE
20-70'	LIME
70-138'	SHALE
138-245'	LIME
245-275'	SAND WATER
275-297'	SHALE
297-394'	LIME
394-400'	BLACK SHALE
400-422'	LIME
422-426'	BLACK SHALE GAS
426-446'	LIME
446-448'	BLACK SHALE
448-450'	LIME
450-622	SHALE
622-632	LIME
632-640	SHALE
640-655	LIME
655-709	SHALE
709-710	LIME
710-717	BLACK SHALE W/COAL
717-730	LIME
730-742	SHALE
742-746	LIME
746-760	SHALE
760-788	LIME
788-792	BLACK SHALE
792-794	LIME
794-838	SHALE
838-858	SAND W/SHALE STREAKS
858-891	SHALE
891-893	LIME
893-898	SHALE
898-908	SAND
908-1172	SHALE
1172-1181	MISSISSIPPI
1181-1186	ODOR
1186-1188	LIME
1188-1198	OIL - OIL ON PIT
1198-1240	LIME

411' GAS TEST 0" ON 1/2" ORIFICE

436' GAS TEST 13" ON 1/2" ORIFICE

737' GAS TEST 3" ON 1/2" ORIFICE

813' GAS TEST 18" ON 1/2" ORIFICE

1176' - 1178' ODOR

1240' T.D.