

L S Well Service
543-A 22000 Rd.
Cherryvale, KS 67335
620-328-4433

DRILLER LOG

Robert Christenson
C S OIL

DIVER #11
API#207-26798-00-00
SEC. 33, T23, R17E
WOODSON CO, KS

3-15-03 Drilled 11 1/4" hole and set 46'
of 8 5/8" surface pipe and set with 30 sx.
of Portland cement.

3-22-03 Started drilling 5 7/8" hole

3-22-03 Finished drilling to T.D. 1214'

0-5	DIRT
5-35'	RIVER ROCK
35-40	LIME
40-130	SHALE
130-240	LIME
240-245	SHALE
245-270	SAND WATER
270-290	SHALE
290-380	LIME
380-385	SHALE
385-410	LIME
410-415	SHALE
415-435	LIME
435-600	SANDY SHALE
600-630	LIME
630-703	SANDY SHALE
703-710	LIME
710-740	SHALE
740-770	LIME
770-775	SHALE
775-780	LIME
780-785	SHALE W/COAL
785-788	LIME
788-826	SANDY SHALE
826-830	SAND OIL
830-835	SHALE
835-838	SAND OIL
838-870	SHALE
870-872	COAL
872-880	SHALE
880-881	LIME
881-883	COAL
883-916	SHALE
916-918	COAL
918-980	SHALE
980-982	COAL
982-995	SHALE
995-1000	RED BED
1000-1152	SHALE
1152-1163	MISSISSIPPI
1163-1168	SHALE
1168-1214	LIME

GAS

712' GAS TEST 30" ON 1/2" ORIFICE

1156'-1157' ODOR

1161'-1163' ODOR

1214' T.D.