

36-23-21E

State Geological Survey
WICHITA BRANCH

Page 1 of 2
Well 36 - 6

AFFIDAVIT AND COMPLETION FORM

ACO-1

This form must be filed in triplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within five days after the completion of the well, regardless of how the well was completed. Circle one: Oil gas, dry, SWD, OWWO, injection. Please type. Complete ALL sections. Applications must be filed for dual completion, commingling, salt water disposal and injection. Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.) KCC#-(316) 263-3238.

OPERATOR KHYBER CORPORATION API NO. 15-011-21,047
ADDRESS 897 East Goorman Avenue COUNTY Bourbon
Littleton, Colorado 80212 FIELD Davis/Bronson Field
**CONTACT PERSON Doyle L. Scroggs LEASE Bradley, et al
PHONE (303) 572-8449

PURCHASER Koch Oil Company WELL NO. 36 - 6
ADDRESS P O Box 2256 WELL LOCATION 345'FWL, 690'FSL SW/4
Wichita, Kansas 67201 345'Ft. from West Line and
690'Ft. from South Line of
the SW/4 SEC. 36 TWP. 23S RGE. 21E

DRILLING CONTRACTOR Teton Exploration
ADDRESS P O Drawer A-1
Casper, Wyoming 82602

PLUGGING CONTRACTOR _____
ADDRESS _____

TOTAL DEPTH 759 PBD _____

SPUD DATE 9-16-81 DATE COMPLETED 9-17-81

ELEV: GR _____ DF _____ KB _____

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS

Report of all strings set — surface, intermediate, production, etc. (New)/(Used) casing.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs./ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface Casing	7 7/8"	6 5/8"	1.25 lb	20'	None	None	None
Production	5 1/4"	2 7/8"	6.5 lb.	714.5'	Portland	70	Gel 3 sacks

LINER RECORD

Top, ft.	Bottom, ft.	Sacks cement

TUBING RECORD

Size	Setting depth	Packer set at


PERFORATION RECORD

Shots per ft.	Size & type	Depth interval
2	2 1/8 glass aluminum strip jets	655-660

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used

Depth interval treated



WELL
PLAT
(Quarter)
or (Full)
Section -
Please
indicate.

KLS✓

36-23-21E

Name of lowest fresh water producing stratum _____ Depth _____
 Estimated height of cement behind pipe _____

WELL LOG

Show all important zones of porosity and contents thereof; cased intervals, and all drill-stem tests, including depth interval tested, cushion used, time test open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Oxidized red clay	0	25		
Oxidized limestone	25	36		
Limestone	36	46		
Gray shale	46	48		
Limestone	48	52		
Gray shale	52	55		
Black shale	55	57		
Limestone	57	60		
Black shale	60	61		
Gray shale	61	63		
Limestone	63	85		
Black shale	85	87		
Gray shale	87	88		
Limestone	88	92		
Gray shale	92	93		
Limestone	93	94		
Gray shale	94	97		
Limestone	97	100		
Gray shale	100	104		
Limestone	104	113		
Gray shale	113	115		
Limestone	115	116		
Dark gray shale	116	119		
Gray shale	119	281		
Limestone	281	290		
Gray shale	290	293		
Limestone	293	302		
Limey shale	302	308		
Limestone	308	312		
Gray shale	312	367		
Coal	367	369		
Gray shale	369	371		
Limestone	371	392		
Black shale	392	394		
Limestone	394	400		
Black shale	400	412		
Gray shale	412	426		
Limestone	426	428		
(Continued)				

A F F I D A V I T

STATE OF COLORADO, COUNTY OF DENVER SS,

DOYLE L. SCROGGS OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH, DEPOSES AND SAYS:

THAT HE IS PRESIDENT FOR KHYBER CORPORATION
 OPERATOR OF THE BRADLEY LEASE, AND IS DULY AUTHORIZED TO MAKE THIS
 AFFIDAVIT FOR AND ON BEHALF OF SAID OPERATOR THAT WELL NO 36-6 ON SAID LEASE HAS

Name of lowest fresh water producing stratum _____ Depth _____
 Estimated height of cement behind pipe _____

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Dark gray shale	428	433		
Gray shale	433	442		
Limestone	442	461		
Black shale	461	468		
Limestone	468	473		
Gray shale	473	475		
Limestone	475	476		
Gray shale	476	540		
Limestone	540	541		
Sandy gray shale	541	570		
Limestone	570	572		
Gray shale	572	583		
Limestone	583	588		
Gray shale	588	604		
Limestone	604	607		
Gray shale	607	625		
Black shale	625	638		
Gray shale	638	644		
Sandy siltstone	644	659		
Core - oil stone	659	679		
Gray shale T. D.	679	759		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

A F F I D A V I T

STATE OF COLORADO, COUNTY OF DENVER SS,

Doyle L. Scroggs OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH, DEPOSES AND SAYS:

THAT HE IS President FOR Khyber Corporation
 OPERATOR OF THE Bradley LEASE, AND IS DULY AUTHORIZED TO MAKE THIS
 AFFIDAVIT FOR AND ON BEHALF OF SAID OPERATOR, THAT WELL NO. 36 - 6 ON SAID LEASE HAS