

WELL LOG BUREAU, KANSAS GEOLOGICAL SOCIETY
 UNION NATIONAL BANK BLDG., WICHITA, KANSAS

CASING RECORD

LOCATION 330'S 330'W N $\frac{1}{4}$ corner.
 (NEcNW)

SEC 21T23 R 11E.

20" 10" 1040 FARM Edward NO. 1 COUNTY Greenwood.
 15 1-2 8 1-4 1570 COMPANY Empire Gas and Fuel.
 12 1-5 93 6 5-8 1922 CONTRACTOR
 5 3-16 COMMENCED 11-21-26 COMPLETED 12-10-26
 TOTAL DEPTH SHOT QUARTS BETWEEN



CORRESPONDENCE REGARDING THIS WELL SHOULD BE REFERRED TO Empire Gas & Fuel Co
 ElDorado, Kansas., ELEVATION

FIGURES INDICATE BOTTOM OF FORMATIONS.
 REMARKS 1-22-27

INITIAL PRODUCTION 350 bbls.

Formation	Depth	Formation	Depth.
soil	10	slate	1680
shale and lime	85	lime	1695
slate	230	slate and lime shells	1705
lime	235	slate	1918
slate and lime shells	300	sand	1922
lime	340	sand	1971
slate	345	shale	1972
lime	350	T.S.	1918 SLM
slate	390	6-5/8 pipe at 1922	
lime	430	T.D.	1972
slate	440	Best Pay	1928-64
lime	450		
slate	455	shot 12-13-26 with 150 qts	
lime	475	1928-1964	
slate	505		
lime	530	Swabbing 12-14-26 150 bbls.	
slate	535	oil no water 18 hours.	
lime	540		
slate and shells	590	12-14-26 350 bblsk oil no wtr	
slate and lime shells	620	24 hours.	
lime	660	12-16-26 180 bbls oil no wtr	
slate and lime shells	700	21 hours.	
slate and lime shells	770		
slate	820		
lime	825		
slate	835		
lime	837		
water sand	910		
slate	920		
lime	965		
sdylime	985		
lime	1030		
sand	1035		
lime	1040		
slate	1056		
lime	1135		
slate	1145		
slate	1270		
lime $\frac{1}{2}$ BW 1330	1435		
slate 2BW 1430	1545		
lime	1555		
slate cave	1575		
lime	1590		
shale	1635		
lime	1640		
shale	1665		
lime	1670		