

UNION NATIONAL BLDG, WICHITA, KANSAS

Location NE NW SE

Sec. 21 T.23 R. 11E.

Casing Record

County- Greenwood.


10" 1005
 20" 8 1/2" 1532
 15 1/2" 65/8" 1860
 12 1/2" 555 53/16"
 Total Depth 1900'.

Farm- D. A. Edwards
 Company- The Texas Co.
 Contr.- George Hinkle
 Comm.- 11/26/28.

No. 1-C.

Comp.- 12/28/1928.

Shot 90 Quarts Between 1876-1897'.
 Correspondence Regarding This Well Should Be Referred to



Elevation

Figures Indicate Bottom of Formations.

Initial Production 100 bbls.

Date Issued. 1/12/1929.

Formation	Depth	Formation	Depth
collar	6	slate white cave sft	1523
lime white hrd	35	lime white hrd	1538
shale blue sft	45	Set 1532' 8 1/2" csg.	
lime drk med.	55	shale blue sft	1600
shale blue sft	75	lime white hrd	1608
shale white sft	145	shale blue sft	1620
shale drk sft	165	shale blue sft	1630
lime drk hrd	195	lime white hrd	1635
shale blue sft	250	shale lgt sft	1645
lime grey hrd	305	lime grey hrd	1655
shale blue sft	310	shale lgt sft	1670
lime grey hrd	325	lime white hrd	1675
shale drk sft	345	shale drk sft	1840
lime grey hrd	355	lime shelly	1842
shale brown sft	365	shale grey sft	1850
lime grey hrd	380	shale black sft	1854
shale blue sft	385	cap rock grey hrd	1855
lime grey hrd	400	Cable measurement.	
shale grey sft	410	lime SLM	1860
lime grey hrd	430	sand brown med.	1898
shale lgt sft	445	Set 6 5/8" csg. at 1860'	
lime grey hrd	450	shale drk sft	1900
shale drk sft	480		
lime drk sft	500	Total Depth SLM	1900'
lime grey hrd	530		
shale lgt sft	550	Top sand	1860'
lime grey hrd	560	First oil	1870
Set 12 1/2" at 555'			
shale drk sft	580		
lime grey hrd	620		
shale grey sft	635		
lime white med.	650		
shale grey sft	660		
lime grey hrd	670		
shale blue sft	690		
lime shells grey sft	710		
shale drk sft	805		
lime white hrd	810		
sand gray hrd	850		
Little water 815'			
sandy shale sft	865		
lime white hrd	900		
shale blue sft	905		
lime grey hrd HFW	935		
shale blue sft	940		
lime white hrd	987		
shale blue sft	992		
lime white hrd	1065		
Set 10" at 1005'			
shale lgt sft	1070		
lime white hrd	1075		
shale lgt sft	1085		
lime white hrd	1090		
shale white sft	1110		
lime white hrd	1118		
shale white sft	1210		
1 1/2 B at 1275'			
lime white hrd	1375		
shale white sft	1385		
shale blue med.	1502		
lime white hrd	1511		