

UNION NATIONAL BANK BLDG WICHITA KANSAS.


Location. SW NW SE

Sec. 21 T. 23 R. 11E.

330' fr NL and WL. of W $\frac{1}{2}$ SE $\frac{1}{4}$

Casing Record.

10" 1000 Farm. D.A. Edwards No. C-3 County. Greenwood.
 20" 8 $\frac{1}{4}$ " 1654 Company. The Texas Company.
 15 $\frac{1}{4}$ " 65/8" 1872 Contr. G.W. Hinkle.
 12 $\frac{3}{8}$ " 574 53/16" Comm. 5-4-29 Comp. 5-29-29
 Total Depth. 1967 Shot 260 Quarts Between 1889-1963
 Correspondence Regarding This Well Should Be Referred To:



Elevation.

Figures Indicate Bottom of Formations.

Initial Production. 225 bbls.,

Date Issued. 6-22-29

Formation	Depth	Formation	Depth.
cellar yellow soft	5	run 10" casing 1000	
lime white hard	15	shale blue soft	1000
shale blue soft	25	lime white hard	1005
lime white hard	35	shale blue soft	1010
shale blue soft	40	lime white hard	1090
lime white hard	55	shale bluesoft	1220
slate white soft	70	LBWPHR 1085	
shale blk soft	85	lime white hard	1240
lime white hard	89	shale blue soft	1245
slate blue soft	95	lime white hard	1380
shale grey soft	115	3BW 1354	
shale blue soft	125	shale blue soft	1385
lime grey hard	130	lime grey hard	1390
shale light soft	150	shale blue soft	1515
blue mud(shale)blue soft	187	lime blue hard	1525
lime grey hard	194	shale blue soft	1530
shale blk soft	197	Bad cave 1515	
lime white hard	200	lime white hard	1560
shale blk soft	265	hole caving 1 $\frac{1}{2}$ BW 1560.	
lime grey hard	290	shale light soft	1600
shale grey soft	307	lime grey hard	1607
lime grey hard	314	shale blue soft	1612
shale blue soft	325	lime grey hard	1615
lime white hard	330	shale blue soft	1649
shale dark soft	355	run 8 $\frac{1}{4}$ " casing 1654	
lime grey hard	376	lime white hard	1654
shale blk soft	380	run 8 $\frac{1}{4}$ " casing 1654 pipe measur.	
lime grey hard	390	shale blue soft	1664
shale light soft	405	lime white hard	1670
lime grey hard	415	slate and shells gr med	1700
shale blue soft	425	shale light soft	1720
lime grey hard	436	lime white hard	1724
shale grey soft	450	shale blue soft	1770
lime white hard	462	lime shells grey hard	1775
slate white soft	480	shale dark soft	1785
shale (blue mud) blue soft	485	shale light soft	1840
lime grey hard Bad.	515	shale dark soft	1855
slate break blue soft cave	519	shale light soft	1862
lime white hard at 485	525	lime light hard	1864
lime grey hard	545	sdv shale brown soft	1874
shale blue soft	572	SLM Total Depth sand	1967
lime white hard	630		
12 $\frac{3}{8}$ 574 shale blk sft	640	6-5/8 1874	
slate white soft	652	Remarks.	
lime white hard	660	Top of sand	
shale white soft	700	SLM 1874	
lime white hard	705	1st good sh	
shale bluesoft	830	of oil 1880-86	
water sand grey soft	880	free oil 86-1964	
HFW 835			
lime white hard	896		
shale light soft	935		
lime grey hard	950		
shale brown soft	960		
lime grey hard	965		
shale blue soft	975		
lime white hard	990		