

Location SW/c SW/4

Sec. 22 T. 23 R. 11E

Casing Record

County- Greenwood

10" 970 Farm- Patterson No.1
 20" 8 1/4" 1630 Company- T. K. Simmons et al
 15 1/8" 65/8" 1877 Contr.- Shull Drlg. Co.
 12 3/8" 583 53/16" Comm.- 8-21-29 Comp.- 9-7-29
 Total Depth 1953 Shot 220 Quarts Between 1892-1950
 Correspondence Regarding This Well Should Be Referred to



Elevation

Figures Indicate Bottom of Formations.
 Date Issued. 9-21-29

Initial Production 590 bbls.

Formation	Depth	Formation	Depth
cellar	5	lime wh	1390
shale yellow	15	shale gray	1515
lime wh	25	lime wh	1520
shale blue	30	shale wh	1525
lime wh	35	shale wh Cave	1535
shale lgt	90	lime wh	1550
lime wh	100	shale wh	1580
shale lgt	165	shale gray	1600
lime wh	190	lime wh	1605
shale blue	245	shale drk	1610
lime wh	270	shale lgt	1630
shale blue	275	lime wh	1640
lime wh	290	shale blue	1650
shale wh	295	lime wh	1670
lime wh	300	shale wh	1720
shale gray	335	shale blk	1770
lime wh	350	lime wh	1775
shale wh	360	shale wh	1783
red rock	365	lime wh	1790
lime wh	390	shale blk	1805
shale blue	400	shale gray	1842
lime wh	425	shale blk	1850
shale lgt	430	shale gray	1865
lime wh	450	shale blk	1880
shale lgt	480	sand gray	1887
lime wh	505	Smell Oil @ 1880'	
shale blue	520	First S.O. 1885'	
lime wh	525	Reduced Hole 1877'	
shale gray	555	sand gray	1950
lime wh	560	shale blk	1953
shale gray	580	TD	1953
lime wh	610	Anchor 2 feet.	
slate blk	620	Pulled 232'6" of	
lime wh	640	6-5/8" casing on	
shale gray	825	top of shot.	
sand wh HFV	860		
shale gray	865		
sdv shale gray	900		
sdv lime wh	935		
lime wh hrd	1085		
shale gray	1215		
lime wh	1230		
shale gray	1235		
lime wh	1250		
shale gray	1260		
lime wh	1330		
sand blk	1335		
lime wh	1360		
shale blk	1365		