

UNION NATIONAL BANK BLDG., WICHITA, KANSAS.

Location NW cor SW SW/4
330' fr W & 1200' fr SL W/2 SW/4

Sec. 22 T. 23 R. 11E.

Casing Record

County - Greenwood.

10" 975 Farm- Patterson No. 3
20" 8 1/2" 1690 Company- T. K. Simmons et al.
15 1/2" 65/8" 1904 SLM Contr.- Shull Drlg. Co.
12 1/2" 615 53/16" Perm.- 11/4/1929. Comp.- 11/30/29
Total Depth 1992 SLM Shot 220 Quarts Between 1929-1989
Correspondence Regarding This Well Should Be Referred to



Figures Indicate Bottom of Formations.
Date Issued. 12/21/1929.

Elevation
Initial Production 532 bbls
24 hrs.

Formation	Depth	Formation	Depth
soil	5	shale lgt	1245
clay yellow	15	lime white Oil Show	1275
shale blue	40	shale white	1285
lime white	45	lime white	1355
shale blue	50	shale black	1360
lime white	55	lime white	1385
shale gray	110	shale black	1390
lime white	120	lime white	1415
shale gray	165	shale gray	1540
shale blue	190	lime white	1545
lime white	215	shale caving	1555
shale white	220	lime white	1575
shale gray	270	shale blue	1580
lime white	295	lime white	1585
shale blue	300	shale gray	1625
lime white	325	lime white	1630
shale black	330	shale lgt	1655
lime white	340	lime white	1660
shale gray	365	shale black	1675
lime white	375	Set 8 1/2" csg. at 1658'	
shale gray	385	lime white	1700
red rock	395	shale gray	1745
lime white	420	8 1/2" collapsed-pulled out	
shale white	435	Re-Run 8 1/2" at 1690'	
lime white	445	shale brown	1780
shale gray	455	shale drk	1810
lime white	460	shale white	1825
shale gray	515	shale drk	1850
lime white	540	shale gray	1880
shale blue	550	shale lgt	1900
lime white	555	shale drk	1905
shale gray	585	Set 6 5/8" pipe at 1904 SLM	
lime white	590	shale sdy lgt	1930
shale gray	610	sand	1991
lime white	615	slate black	1992
Set 12 1/2" csg. at 615'		TD SLM	1992
lime white	640		
slate black	655	First oil showed at 1931	
lime white	665		
shale gray	850		
lime gray	855		
sand gray HFW	890		
shale gray	915		
lime sdy gray	935		
lime sdy white	965		
slate white	970		
lime white	975		
Set 10" csg. at 975'			
lime white	1015		
shale blue	1020		
lime white	1115		