

44

24-23-10E

41229

WELL LOG BUREAU, KANSAS GEOLOGICAL SOCIETY
BITTING BUILDING, WICHITA, KANSAS

CASING RECORD

LOCATION

SEC 24 T 23 R 10 E

10" 992 FARM **Burkett Farm** NO. **4** COUNTY **Greenwood**
 20" 8 1-4 1654 COMPANY **Tidal Oil Company**
 15 1-2 6 5-8 1916 CONTRACTOR
 12 1-2 605 5 3-16 COMMENCED **April 28, 1923** COMPLETED **May 23, 1923.**

	24	

TOTAL DEPTH **2115** SHOT **120** QUARTS BETWEEN **2062-2110**

CORRESPONDENCE REGARDING THIS WELL SHOULD BE REFERRED TO **Tidal Oil Company,**
Tulsa, Oklahoma.

ELEVATION INITIAL PRODUCTION **45 bbls Natural**

FIGURES INDICATE BOTTOM OF FORMATIONS

REMARKS

Formation	Depth
soil	10
shale brown	30
shale white	150
lime white	175
shale blue	330
lime	370
shale	490
lime	645
shale	680
lime (Set 12 1/2" at 680')	690
slate	745
lime	755
shale	770
lime	830
shale	1005
sand	1115
shale	1140
water sand	1145
slate (Set 10" at 1150)	1150
lime	1260
slate	1285
lime	1290
slate	1390
lime	1570
shale	1610

Formation	Depth
water sand	1620
shale	1702
lime (Set 8 1/2" at 1705)	1707
shale lime shell	1960
slate black	2010
sandy shale	2025
Top Oil sand	2025
(Set 6 5/8" at 2025)	
bottom & T. D.	2115.