

WELL LOG BUREAU, KANSAS GEOLOGICAL SOCIETY

Union National Bank Bldg., Wichita, Kansas

24-23-10E

LOCATION C WL SW NW NW.
 CASING RECORD 990' NL & 330' fr WL.
 10" 1141 FARM Burkett
 20" 8 1-4 1400 COMPANY Tidal Oil Co.
 15 1-2 6 5-8 2050 CONTRACTOR
 12 1-2 690 5 3-16 COMMENCED 2/22/1923.

SEC 24 T 23 R 10E.

NO. 3 COUNTY Greenwood.

COMPLETED 3/26/1923.

TOTAL DEPTH SHOT 120 QUARTS BETWEEN 2070-2118

CORRESPONDENCE REGARDING THIS WELL SHOULD BE REFERRED TO

FIGURES INDICATE BOTTOM OF FORMATIONS
 DATE ISSUED

ELEVATION
 INITIAL PRODUCTION 100 bbls
 natural, 150 bbls after shot.

Formation	Depth
soil sft	35
lime hrd	90
1 BW/hr at 95	
sand	100
lime	125
shale	150
lime	200
shale	225
lime	250
shale	280
lime	300
shale	350
shale	400
lime	440
sand 2 BW at 450'	450
lime	500
shale	525
lime	550
shale	660
lime Set 12 $\frac{1}{2}$ " 670	670
slate	720
lime	770
lime	805
shale	830
lime	890
shale	950
sand water	985
lime	1000
HFV at 995'	
sand	1095
sand	1133
lime	1163
Set 10" at 1141'	
lime	1263
shale	1310
slate	1380
slate	1422
Set 8" at 1400'	
lime	1505
shale	1550
slate	2020
sand	2028
slate	2050
Set 6 5/8" at 2050'	
top of oil sand	2050
TD	2144