27-23-16E Ind PC

TYPE ★ AFFIDAVIT OF COMPLETION FORM ACO-1 WELL HISTORY

SIDE ONE State Geological Survey Compt.____

WICHITA BRANCH

(Rules 82-3-130 and 82-3-107)
This form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ninety (90) days after the completion of a well, regardless of how the well was completed.

FOR INFORMATION REGARDING THE NUMBER OF COPIES TO BE FILED AND APPLICATIONS REQUIRING COPIES OF ACO-1 FORMS SEE PAGE TWO (2), SIDE TWO (2) OF THIS FORM.

F ____ Letter requesting confidentiality attached.

C ____ Attach ONE COPY of EACH wireline log run (i.e. electrical log, sonic log, gamma ray neutron log etc.)***Check here if NO logs were run____.

PLEASE FILL IN ALL INFORMATION. IF NOT AVAILABLE, INDICATE. IF INFORMATION LATER BECOMES AVAILABLE, SUBMIT BY LETTER.

LICENSE # 5983 EXPIRATION DATE 6/30/83

OPERATOR Victor J. Leis API NO. 15-207-24,129

ADDRESS Box 223 COUNTY Woodson

Yates Center, Kansas 66783 FIELD ____

** CONTACT PERSON Victor J. Leis PROD. FORMATION Squirrel

PHONE 316-625-2601

PURCHASER K. Maclaskey Oil Purchasing LEASE Ross "A"

ADDRESS Box 222 WELL NO. 13

ElDorado, Kansas 67042 WELL LOCATION SE/4 SW/4 SW/4


DRILLING CONTRACTOR Leis andDavis Drilling 560 Ft. from South Line and

ADDRESS Box 62 1050 Ft. from West Line of

Yates Center, Kansas 66783 the ~~SW4~~ (Qtr.) SEC 27 TWP 23 RGE 16~~X~~(W). (E)

PLUGGING CONTRACTOR ADDRESS ____

WELL PLAT



(Office Use Only)
KCC ✓
KGS ✓
SWD/REP_
PLG.____
NGPA____

TOTAL DEPTH 1102 PBTD 1100

SPUD DATE 2/14/83 DATE COMPLETED 2/16/83

ELEV: GR 1078 DF ____ KB ____

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE ____.

Amount of surface pipe set and cemented 40 feet DV Tool Used? ____.

TYPE OF COMPLETION THIS AFFIDAVIT APPLIES TO: (Circle ONE) - (Oil), Shut-in Gas, Gas, Dry, Disposal, Injection, Temporarily Abandoned. If OWWO, indicate type of re-completion ____. Other completion ____. NGPA filing ____.

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

A F F I D A V I T

Victor J. Leis, being of lawful age, hereby certifies that:

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit.

State Geological Survey
WICHITA BRANCH

SIDE TWO

ACO-1 WELL HISTORY

OPERATOR Victor J. Leis LEASE Ross A SEC. 27 TWP. 23 RGE. 16 (E) (W) XXX

FILL IN WELL INFORMATION AS REQUIRED: WELL NO. A-13

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
____Check if no Drill Stem Tests Run.				
____Check if samples sent to Geological Survey				
Topsoil	0	2		
Clay	2	11		
Lime	11	12		
Clay	12	17		
Shale	17	172		
Lime	172	178		
Shale	178	225		
Lime	225	260		
Shale	260	294		
Lime	294	432		
Lime-soft	432	473		
Lime	473	485		
Shale	485	536		
Lime B-KC	536	664		
Shale-broken	664	850		
Lime	850	863		
Shale	863	927		
Lime-broken	927	959		
Shale	959	970		
Lime	970	981		
Shale	981	992		
Lime	992	996		
Shale	996	1002		
LIme 5'	1002	1005		
Shale	1005	1010		
Lime	1010	1011		
Shale	1011	1051		
Sand-OIL	1051	1060		
Shale	1060	1102		
T.D.		1102		

If additional space is needed use Page 2,

Report of all strings set — surface, intermediate, production, etc. CASING RECORD (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	10"	6 5/8'		40'	Portland	7	none
Casing	5 1/8"	2 7/8'		1102	RFC	130	none

LINER RECORD | PERFORATION RECORD

Date of first production	Producing method (flowing, pumping, gas lift, etc.)	Gravity
2-20-83	Pumping	24

Estimated Production -I.P.	Oil	Gas	Water	Gas-oil ratio
	10 bbls.	MCF	1% ½ bbls.	CFPB

Disposition of gas (vented, used on lease or sold): used on lease

Perforations