

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- T. K. SIMMONS ET AL
Farm- Ellis No. 3-B

SEC. 27 T. 23 R. 11E
NW SE NW

OLD WELL DRILLED DEEPER

Total Depth. 19 62

Comm. 4-3-30


Comp. 4-18-30

County Greenwood
KANSAS

Shot or Treated.

Contractor. Shull Drlg. Co.

Issued. 2-21-53



CASING:

12 1/2" 545' 6 5/8" 1863'
10" 939'
8 1/4" 1525'

Elevation. _____

Production. 60 bbls.

Figures indicate Bottom of Formations.

lime	20	shale drk	1705	Gamma Ray Neutron log was run at 1953 RKB indicating the above formation markers.
shale lgt	50	shale lgt	1760	
lime wht	60	lime lgt	1765	
shale lgt	80	shale lgt	1830	
shale lgt	145	shale drk	1840	
lime wht	170	shale lgt	1850	Water injection begun 1-3-53
shale lgt	230	shale blk	1860	
lime lgt	280	shale lgt	1883	All casing was pulled during plugging operations.
shale blue	300	sand lgt dry	1912	
shale drk	325	sand oil	1943	
sand lgt	335	shale drk	1947	
lime wht	340	Old Well Drilled Deeper	T.D.	
red rock	350	Company - Phillips Petro.		
lime wht	355	Farm - Beal Unit "H" No. W-6		
shale lgt	385	Comm. - 11- 1-52		
lime lgt	400	Comp. - 11-21-52		
shale lgt	425	old plugged well H-10		
lime wht	435			
shale lgt	470	sand & shale	1962 RKB	
lime wht	495	Total Depth		
shale lgt	545			
lime wht	550	Tops:		
shale lgt	570	Howard	150	
lime lgt 1 BW	595	Topeka	233	
shale lgt	600	Heebner	600	
lime lgt	605	Toronto	614	
shale drk	615	Douglas	630	
lime lgt	625	Tonganoxie Sand	806-855	
shale lgt	810	Tonganoxie Sand	874-923	
lime lgt	815	Lansing-Kansas City	923	
shale lgt	835	Drum	1202	
sand lgt HFW	860	Base-Kansas City	1366	
shale lgt	870	Marmaton	1487	
lime wht sandy	915	Cherokee	1660	
shale drk	920	Bart. Zone	1872	
lime wht sandy	925	Shaley Sand	1872-1882	
shale lgt	930	Sandy Shale	1883-1894	
lime lgt	939	Shaley Sand	1894-1905	
lime wht	1070	Shale	1905-1909	
shale gry	1205	Sandy shale & shaley		
lime wht	1300	sand	1909-1917	
1 1/2 BW 1290-1300'		Bart. Sand	1917	
lime gry	1355	Sand	1917-1944	
lime wht	1370	Sandy shale & shaley		
shale lgt	1410	sand	1944-1948	
shale gry	1500	Shaley sand	1948-1950	
lime gry	1505	sandy shale	1950-1951	
shale wht cave	1525	T.D.	1953	
lime wht	1540			
shale wht	1545	Phillips Petro. Rig # 39		
shale gry	1595	drilled & washed down old hole to		
lime gry	1605	1947 G.M. O.T.D.		
shale gry	1615	Formation given encountered by		
lime gry	1625	rotary & cable tools in deepening.		
lime, shells lgt	1660	Unable to be specific on account		
shale lgt	1685	of hole caving		

Prior to drilling additional
hole w/cable tools, Lane Wells