

Kelly Down Drilling Co., Inc.

K. W. Laymon
Drilling Contractor
&
Oil Producer

28 23 14E

Route 1 P. O. Box 85

Neosho Falls, Kansas 66758

Phone: (316) 963-2495

September 25, 1984

French & Winterscheid, Inc.

Gridley, Kansas 66852

Figures indicate bottom of formation

Soil & Clay	16
Shale	79
Lime	84
Shale & Lime	721
Sandy Lime	768
Lime	777
Black Shale	779
Lime	782
Shale	828
Shale & Lime	923
Black Shale	927
Lime	933
Gas odor	933
Lime & Shale	1197
Lime	1204
Shale	1224
Lime	1251
Shale	1633 ¹ ₂
Mississippi Lime	1644
Sand	1646
Lime	1650
Sand	1663
Lime	1680
Total Depth	1680

Figge No. 20
Spudding Date: 9/20/84
Completion Date: 9/25/84
Bit Size: 6¹/₂"
1,830' from North line
1,465' from West line
Sec 28-23-14E Woodsn Co.

Cementing record:

Surface cemented with 10 sack
of Portland.
Production string cemented
with 150 sack Bulk cement,
Pozmix added.

RECEIVED
STATE CORPORATION COMMISSION

OCT 23 1984

CONSERVATION DIVISION
Wichita, Kansas

Set 42.50' of 7" surface.
Ran 1,678¹/₂' of 4¹/₂" pipe.

State Geological Survey
WICHITA BRANCH

Perforated with 8 shots at 1647-1654. Pumped out fresh water. Tested 36 hours, showed only small amount of oil. OCT. 4, 1984: Acidized with 2,000 gallons 15% and flushed with 25 barrels water. First 17 hours 25 barrels of oil. Next 24 hours 15 barrels oil. On Oct. 11 it was making 8 barrels of oil and very little water.