

28-23-10E

6919

LOG OF THRALL WELL #2,  
SECTION 28, TOWNSHIP 23 SOUTH OF RANGE 10 EAST  
GREENWOOD COUNTY, KANSAS.

MISSION OIL COMPANY,

TOTAL DEPTH 2329 Feet

FORMATION	THICKNESS	TOTAL DEPTH	REMARKS
Lime	40	40	
Shale	50	90	
Lime	40	130	
Shale	170	300	
Lime	20	320	
Shale	40	360	
Lime	30	390	set 12 1/2" Casing 390 feet
Shale	60	450	
Lime	15	465	
Shale	50	515	
Lime	95	610	
Shale	110	720	
Lime	7	727	
Shale	8	735	
Lime	5	740	
Shale	15	755	
Lime	23	778	
Shale	22	800	
Lime	27	827	
Shale	33	860	
Lime	20	880	
Shale	30	910	
Lime	7	917	
Shale	57	974	
Lime	16	990	
Shale	20	1010	
Lime	45	1055	
Shale	5	1060	
Lime	25	1085	
Shale	15	1100	
Lime	12	1112	
Shale	138	1250	set 10" Casing 1243 feet.
Sand	8	1258	
Shale	12	1270	Hole Full Water
Sand	20	1290	
Shale	60----- 1350	1350	
Lime	5	1355	
Shale	4	1359	
Lime	141	1500	set 8" Casing 1475 feet
shale	125	1655	
lime	120	1745	
shale	3	1748	
lime	52	1800	
white shale	90	1890	
black s hale	25	1915	
lime	2	1917	
shale	20	1937	cave
lime	10	1947	
shale	10	1957	
lime	40	1997	
shale	91	2088	
lime	10	2098	
Shale	242	2240	
sandy shale	9	2249	
shale	5	2254	
black shale	5	2259	
light shale	5	2264	
shale	14	2278	
sand	4	2282	set 6 5/8" Casing 2280 (Show oil)
sand	3	2285	no showing
sand	4	2289	small showing
sand	22	2311	good pay gas
sand	18	2329	big pay bottom in blue shale.

set 12 1/2" Casing 390 feet  
 28 23 10  
 Thrall No. 2  
 Mission Oil Company  
 Elev. T. D. 2329  
 Log No.

