

3-23-19E ✓

LOG OF BIG INDIAN WELL #2.

Meissner Farm. Section 3-23-19 Anderson County, Kas.
Commenced drilling Nov. 1, 1921.

Plotted

	Feet	
8	Soil	8
2	Gravel	10
8	Lime	18
2	Shale	20
10	Lime	30
45	Shale	75
10	Lime	85
45	Shale	130
50	Lime	180
32	Shale	212
8	Lime	220
30	Shale	250
25	Lime	275
15	Sand	290 Lots of water
20	Lime	310
7	Slate, black	317
5	Lime	322
5	Sand	327 Lots of water
17	Lime	345
5	Shale	350
10	Lime	360
140	Shale	500 Set 8 1/4 casing at 380
10	Lime	510
25	Shale	535
10	Lime	545
5	Shale	550
5	Lime	555
10	Shale	565
10	Lime	575
3	Shale	578
7	Lime	585
25	Shale	610
5	Lime	615
10	Shale	625
15	Lime	640
5	Shale	645 Water
45	Lime	690
15	Shale	705
10	Lime	715
5	Shale	720
10	Lime	730
285	Shale	1015 Set 6-5/8 casing at 948
5	Sand	1020 Water
5	Sand (gas)	1025 No show
80	Shale	1105
5	Lime (Mississippi)	1110
15	Sand	1125 Hole full of sulphur water
35	Lime	1160
35	Sand	1195
5	Lime	1200

Diff

Plotted

Total depth 1200

✓