

Jim Cornish -

Mtg concerning Nestit B-2
w/o Program for B-2 1880?
MIR - Clean out to TD 1855?

(Drld out BP @ 1800)

RU Cornish Well Service

Run GRIN Correlation Log

Perf as follows:

Alum shots Miss 1852-56' (5')

Alum shots Bartlesville 1760-62'; 1750-56' & 1741-48'

" " Cattelman 1725-1742' (17')

Carrier vs Alum shots - on Report use Alum

Run in w/ PKr $\frac{1}{2}$ Tbg

Set PKr approx 1825' (^{20' collar} @ 1820')

Trtd w/ Acid -

RD put on Pump $\frac{1}{2}$ Tbg