


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company. ALADDIN PETROLEUM
Farm- Everett No. 3
LN WN

SEC. 29 T. 23 R. 4E
NE NE NW

Total Depth. 2442'
Comm. 12-4-57 Comp. 12-12-57
Shot or Treated.
Contractor. Crowe Drilling Company, Inc.
Issued. 2-1-58

County Butler
KANSAS



CASING:
8 5/8" 98' cem w/100 sx
5 1/2" 2442' cem w/650 sx

Elevation. 1347' GL

Production. 25 BOPD

Figures Indicate Bottom of Formations.

shale & lime	687
shale & shells	780
shale & lime streaks	1160
lime	1267
shale with lime streaks	1280
lime	1794
shale & lime	1953
Kansas City Lime	2080
shale & lime	2220
lime	2365
Hutton Dolomite	2376
lime	2442
Total Depth	

TOPS:
Kansas City 1953
Hunton 2364

12-15-57 Perf. 74/2392-2410'.
1000 Gal. Acid.
Perf. 32-2380-88'.
Perf. 18/2400-03'.
2000 Gal. Acid.