


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
503 East Mundock, Wichita, Kansas

Company - MAGNOLIA PETRO. CO.
Farm - D. Holdon No. 6

SEC. 4 T. 23 R. 4E
NE SW SW

Total Depth. 2151 PB 2145
Comm. 3-22-52 Comp. 4-25-52
Shot or Treated. Acidized
Contractor. Edwards Drlg. Co.
Issued. 6-7-52

County Butler
KANSAS



CASING:

8 5/8" 102' com. w/50 sx
5" 2151' com. w/100 sx

Elevation. 1131

Production. 4 BO & 7 BW 24 hrs.

Figures indicate Bottom of Formations.

surface hole	102
lime	350
red rock	360
lime	455
shale & shells	765
shale	985
lime	1070
shale, sandy & shells	1350
lime & shale	1480
lime	1640
shale	1770
lime	1815
shale	1842
lime	1950
shale	2010
lime	2111
lime, dense wht to tan	2114
lime, dense, tan w/sat. & stain of lgt oil in fractures	2120
lime drk gry to brn	2124
shale drk gry to blk	2126
lime drk gry dense	2131
lime tan oolitic w/fair stain in fractures	2134
lime tan to brown dense	2140
lime drk gry dense w/ spotted stain of dead oil along fractures	2142
lime gry dense	2151
Total Depth PB 2145	

Tops:
Lansing 1845
Kansas City 2010

Cored from 2111-51:
PB 2145, perf 2098-2118 w/80 sh.,
test 7 GPH w/SSO Acidized w/1000
gals.; swb 10 BO & 17 BW in 24 hrs.