

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **PHILLIPS PETROLEUM**

SEC. **4** T. **23** R. **4E**
 LOC. **SW SE NW**

FARM **Supernaugh** "D" NO. **7**

TOTAL DEPTH **2885**

COMM. **9-22-66**

COMP. **10-2-66**


SHOT OR TREATED

CONTRACTOR **White & Ellis**

ISSUED **11-19-66**

COUNTY **Butler**

KANSAS



CASING

20	10 3/4"	@ 207'	w/120 sx
15	8		
12	6 7"	@ 2612'	w/141 sx
13	5		

ELEVATION **1448'KB**

PRODUCTION SWDW RATE
 SATISFACTORY (Arb
 2612-2885)

FIGURES INDICATE BOTTOM OF FORMATIONS

Kelly Bushing Measurement 5' above ground level.

<u>FORMATION</u>	<u>DEPTH</u>
Shale	0-45
Lime	205
Lime w/Shale	250
Shale & Lime	500
Shale & Lime (stks.)	770
Shale w/Lime stks.	1120
Shale w/Lime (stks.)	1305
Shale & Lime (stks.)	1461
Shale & Lime stks.	1600
Lime w/Shale stks.	1620
Shale	1778
Lime	1788
Shale & Lime	1833
Lime	1908
Lime & Shale stks.	1990
Lime w/Shale stks.	2102
Lime & Shale (stks.)	2200
Lime w/Shale stks.	2290
Shale w/Lime stks.	2410
Shale w/Lime stks.	2418
Lime	2468
Sandy Shale	2510
Sand	2590
Lime	2885

LOG **TDPS**

Kansas City	1633
Hunton	2418
B/Hunton	2450
Viola	2468 2490
Simpson	2510
Arbuckle	2590
SAMPLE TOPS:	
Lansing	1833
Base Kansas City	2204
Kinderhook	2410
Hunton	2418
Viola	2490
Simpson	2510
Arbuckle	2584