

LOG OF HENDRIX #2

5-23-19⁰E✓
Plotted

Colony gas field, Anderson County, Kas.
Started drilling ~~May~~ 30-1921
Finisht " July 10.

Drilled by Limes Bros.
LaHarpe
Elev. 19 ft. below Ewing 2

soil	1
clay	7
lime	60
shale, dark	170
lime	206
shale, light	235
lime	245
shale, dark	275
lime	326
shale, dark	329
slate	332
lime	363
sand, black	367 water
lime	373 5-6 B.
shale, light	378
lime	387
shale, dark	518
" , light	554
lime	557
shale, light	578
lime	587
shale, black	600
" , light	605
" , dark	620
" , light	640
" , sandy	650
lime	656
shale, light	668
lime	673
shale, black	685
(1/4 mil. gas)	
shale, light	706
" , dark	717
lime	722
shale, sandy dark	746
" , light	770
" , dark	815
sand, some gas	860
" , strong gas	881 T.D.

CASING RECORD:

8 1/4 drive-pipe	20ft.
6 1/4 casing	634
4 7/8 "	881

Wall-packer set at 768, with
two joints of perforated
pipe at bottom of string.

Burlap wrapping to catch cavings
set at 909.

Hendrix		No. 2
SEC. 5	TP. 23	R. 19
CO. Anderson		
PL. PROD. 5,000,000 1079		
5		
*		

could not
determine whether
we reached bottom
of sand.

Drill

Plotted