

6-23-19 ✓

LOG OF J. R. ROBERTS WELL

SE cor. City of Colony, 6-23-19 Anderson Co., Kas.
 Finished 9/27/21. Started 9/15/21
 Drilled by Limes Bros., La Harpe, Kansas.

J. R. Roberts	
SEC. 6	TR. 23 R. 19
CO. Anderson	
IN. PROD.	ALT. FEET

Plotted

Casing record:

10"	15'
8 1/4"	535'
6 1/4"	905'

	Feet
Soil	1
Gravel	3
Clay	15
Lime	40
Shale, light	45
Lime	58
Mud Brown	80
Shale, dark	105
Lime	157
Shale, dark	244
Lime	283
Shale, dark	312
Lime	317
Shale, light	322
Shale, black	332
Shale, dark	352
Lime	372
Shale	376
Lime	386
Shale	396
Lime	418
Shale, (Water 8-B)	424
Lime	450
Shale, light	455
Lime	465
Shale, dark, sandy	525
Shale, dark	600
Shale, light, sandy	630
Shale, dark, sandy	636
Lime	639
Shale, white, sandy	660
Lime	672
Shale, light	730
Lime	735
Shale, light	740
Shale, dark	748
Lime	751
Shale, dark	768
Lime	770
Shale, light, sandy	785
Shale, dark	794
Lime	797
Shale, dark, sandy	820
Shale, white, sandy	833
Shale, light	838
Shale, dark	900
Sand	905
Sand Gas	930
Shale	940
Sand Gas	1003

dupl.