

LOG OF SKOURUP WELL #4.

Elev. 1131

7-23-19E
7-23-19E

NW cor. NE NE Sec. 7-23-19, Colony, Anderson Co., Kas.
Commenced drilling 12/14/21; finisht 12/28/21.
Drilled by Limes Bros., La Harpe, Kas.

Plotted

Soil	1
Gravel	3
Clay	8
Lime	18
Shale	28
Lime	59
Shale	90
Lime	148
Shale	240
Lime	280
Shale	292
Lime	294
Shale	313
Lime	319
Shale, light	324
Shale, black	330
Shale, dark	350
Lime	412
Shale, black	417
Lime	442
Shale	445
Lime	454
Shale	456
Lime	468
Shale, light	482
Shale, dark	525
Shale, light	545
Shale, dark	595
Shale, light	620
Shale, dark	628
Lime	634
Shale, light	653
Lime	666
Shale	672
Lime	674
Shale, light	688
Lime	693
Shale	716
Lime	718
Shale	723
Lime	728
Shale	743
Lime	746
Shale, dark	758
Shale, light	790
Lime	792
Shale, dark	820
Shale, light, sandy	855
(Shale, darker at 850)	
Shale, dark	895
Sand	999

Casing record:

10"	12'
8 1/4"	503' pulled
6 1/4"	898'

Water

Pl.

dupl.