

7-23-19 E ✓

LOG OF MAKEMSON NO. I WELL.

NW. cor. NW NE 7-23-19, Colony, Anderson Co. Kas.,
 Finished 9/21/21. Started 9/7/21.
 Drilled by Limes Bros., La Harpe, Kas.

Makemson	
SEC. 7	TP. 23 R 19
CO. Anderson	
IN. PROD.	ACT.
	REMARKS

	Feet.
Soil	1
Gravel	5
Clay, yellow	8
Shale, blue	14
Lime	60
Shale, blue	90
Lime	165
Shale, light	230
Lime	275
Shale, blue	300
Lime	308
Shale, light	313
Shale, blue	345
Lime	412
Shale, black (water)	415
Lime	438
Shale, black (water)	442
Lime	449
Shale, light	450
Lime	467
Shale	472
Lime	474
Shale, light	625
Lime	640
Shale, light	645
Lime	660
Shale, dark	678
Lime	680
Shale, light	695
Sand	714
Lime	730
Shale, dark	740
Lime	748
Shale, blue	751
Lime	758
Shale, white	761
Lime	772
Shale, dark	783
Lime	785
Shale, dark	800
Lime	802
Shale, light	817
Sand	850
Shale, dark	895
Sand	1000 T.D. gas

Casing record:

10"	14'
8 1/2"	494'
6 1/2"	835'

dupl.