


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- CITIES SERVICE PETROLEUM CORP.
Farm- Teter Unit Green No. 16

SEC. 10 T. 23 R. 9E
 SE NW SE

Total Depth. 2386'
Comm. 3-12-62 Comp. 3-24-62
Shot or Treated.
Contractor. White & Ellis Drlg., Inc.
Issued. 5-26-62

County Greenwood
 KANSAS



Elevation. 1412' KB

Production. Input.

CASING:
8 5/8" 203' w/85 sx cem.
4 1/2" 2314' w/140 sx cem.

soil	3	Figures Indicate Bottom of Formations. Ran Schlumberger Induction- Electric & Microlog.
lime	25	
shale	40	
shale, shells	110	
lime	120	
shale	125	
shale, shells	150	
lime	175	
shale	200	
lime	203	
shale, shells	250	
shale, lime stks	345	
shale, shells	490	
lime w/shale stks	730	
shale, shells	1105	
lime	1114	
lime, shale stks	1152	
shale, lime stks	1190	
shale, shells	1297	
lime	1301	
shale	1310	
sand	1385	
sand, shale	1443	
lime	1554	
shale	1689	
lime	1800	
lime, shale stks	1836	
lime	1873	
shale, shells	1990	
lime, shale stks	2205	
shale, shells	2308	
sand	2338	
sand, shale stks	2378	
shale, shells	2386	
Total Depth		

All Meas. from K.B.

<u>Steel Line Meas.</u>	<u>S.H.S.</u>
491' = 492'	491' 1°
1022' = 1022'	1022' 1/2°
1490' = 1490'	1490' 3/4°
2020' = 2020'	2020' 1/8°

TOPS:
Douglas Sd. 1313
Base 1443 N.S.O.

Lansing Ls. 1443
Base 1554 N.S.O.

Kansas City Ls 1691
Base 1886 N.S.O.

Fort Scott Ls. 2118
Base 2155 N.S.O.

Bartlesville Sd. 2308
Base 2379
Best Pay Zone: 2308-40'
FSFO