


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- CITIES SERVICE PET. CO.
Farm- Teter Unit Green No. 12-W

SEC. 10 T. 23 R. 9E
NW NE SE
370' S & 990' W of E/4 cor
(40' fr old hole)
County Greenwood
KANSAS

Total Depth. 2399'
Comm. 3-9-62 Comp. 4-14-62
Shot or Treated.
Contractor. White & Ellis Drlg. Co.
Issued. 9-1-62



Elevation. 1423' K.B. (5' above G.L.)

Production. Input

CASING:
8 5/8" 202' w/85 sx cem.
4 1/2" 2315' w/140 sx cem.

All Meas. fr K.B. Figures Indicate Bottom of Formations.

soil	5
lime	15
shale	20
lime	35
shale	50
lime	85
shale	115
shale, shells	160
lime	165
shale	180
lime	185
shale	200
lime	202
shale, lime shells	290
lime, shale stks	370
shale, shells	420
shale, lime	590
shale, shells	735
shale, lime stks	785
lime	816
shale, lime stks	826
shale w/lime stks	1100
lime	1139
lime, shale stks	1153
shale, shells	1330
shale, sdy. shale	1458
lime	1584
shale	1698
lime	1882
shale, shells	2005
lime	2013
shale, lime stks	2069
shale, shells	2090
lime	2201
shale, shells	2311
sand	2316
Core #1	2346
sand	2352
shale, sand	2362
shale, sdy shale	2399
Total Depth	

TOPS:

Lansing Ls.	1458
Base	1583
Kansas City Ls.	1697
Base	1893 N.S.O. noted.
Cherokee shale	2159
Bartlesville sand	2310
Pen.	89

Core #1 2316-2346' (30') (Rec. 30')

Ran Schlumberger Induction & Microlog.