


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- CITIES SERVICE OIL CO.
Farm- T.U. Green No. 53-W

SEC. 10 T. 23 R. 9E
Approx. C S½ Sec.
1322' N & 15' E of S½ Cor.

Total Depth. 2429'
Comm. 4-3-60 Comp. 4-8-60
Shot or Treated.
Contractor. White & Ellis Drlg. Co.
Issued. 10-22-60

County Greenwood
KANSAS



Elevation. 1443' KB. (5' Above G.L.)

Production. Wtr. Input.

CASING:

8 5/8" 206' w/125 sx cem.
4½" 2384' w/125 sx cem.

Figures Indicate Bottom of Formations.

All Meas. fr K.B.	
lime w/little shale	25
lime	43
lime, shale stks	65
shale, shells	77
lime, shale stks	102
shale, shells	130
shale, lime stks	206
lime	230
shale	990
lime	1112
shale	1129
lime	1147
shale	1222
shale, shells	1345
lime	1352
sand	1470
lime	1503
lime, shale stks	1523
lime	1595
shale, lime stks	1670
shale, lime	1778
lime	1919
shale, shells	2024
shale, lime stks	2290
shale, lime	2347
sand	2350
sand, shale	2504
shale	2429
Total Depth	

<u>Steel Line Meas.</u>	<u>S.H.S.</u>
503' = 503'	503' O.K.
1007' = 1007'	1007' O.K.
1500' = 1500'	1500' O.K.
2011' = 2011'	2011' O.K.

Top Douglas sand	1197
Base	1479 N.S.O.
Top Lansing Ls	1479
Base	1600 N.S.O.
Top Kansas City Ls	1719
Base	1913 N.S.O.
Top Bartlesville Zone	2347
Th.	35 M.S.S.O.
Top Bartlesville (Good)	
Sand	2382
Th.	28 G.S.F.O.
Base	2410

Core #1 - 2351-2404' (53') (Rec. 53')
Core #2 - 2404-2429' (25') (Rec. 25')