



OILFIELD RESEARCH LABORATORIES

536 NORTH HIGHLAND - CHANUTE, KANSAS 66720 - PHONE (316) 431-2650

September 22, 1982

Lamoreaux Homes, Inc.
Box 8
Waterville, Kansas 66548

Gentlemen:

Attached hereto are the results of tests run on the rotary core taken from the Kramer Lease, Well No. 1, located 440' from the North Line and 165' from the West Line in Section 16, T-24S, R-~~16E~~^{17E}, Woodson County, Kansas.

The core was sampled and sealed in plastic bags by a representative of the client and submitted to our laboratory on September 21, 1982.

Your business is greatly appreciated.

Very truly yours,

OILFIELD RESEARCH LABORATORIES


Sanford A. Michel

SAM/pdc

4 c to Waterville, Kansas
1 c to Dick Brooks, Osawatomie, Kansas

OILFIELD RESEARCH LABORATORIESLOGName Lamoreaux Homes, Inc. Lease Kramer Well No. 1Depth Interval,
FeetDescriptionSQUIRREL SAND

866.0 - 867.2

Grayish brown calcareous very shaly sandstone.

867.2 - 868.0

Brown shaly sandstone.

868.0 - 869.0

Grayish brown very shaly sandstone.

869.0 - 869.6

Grayish brown shaly sandstone.

869.6 - 870.4

Gray sandy shale.

Oilfield Research Laboratories

RESULTS OF SATURATION & PERMEABILITY TESTS

TABLE 1

Company Lamoreaux Homes, Inc. Lease Kramer Well No. 1

Sample No.	Depth, Feet	Porosity Percent	Percent Saturation			Oil Content Bbls. / A Ft.	Perm., Mill.
			Oil	Water	Total		
1	866.8	10.6	66	20	86	543	Imp.
2	867.7	16.4	51	26	77	649	3.9
3	868.7	18.8	50	44	94	729	Imp.
4	869.5	16.7	62	18	80	803	1.9