

OILFIELD RESEARCH LABORATORIES

536 NORTH HIGHLAND - CHANUTE, KANSAS 66720 - PHONE (316) 431-2650

March 31, 1980

Beckett Oil Company
620 East Carpenter
Iola, Kansas 66749

Gentlemen:


Attached hereto are the results of tests run on the rotary core taken from the Teats Lease, Well No. 10, located in Allen County, Kansas.

The core was sampled by a representative of Oilfield Research Laboratories after being received in the laboratory on March 20, 1980.

Your business is greatly appreciated.

Very truly yours,

OILFIELD RESEARCH LABORATORIES


Sanford A. Michel

SAM/tem

7 c to Iola, Kansas

OILFIELD RESEARCH LABORATORIES

LOGName Berkett Oil Company Lease Teats Well No. 10

<u>Depth Interval,</u> <u>Feet</u>	<u>SQUIRRELL SAND</u> <u>Description</u>
825.0 - 826.1	Brown shaly sandstone.
826.1 - 828.3	Dark brown sandstone.
828.3 - 829.3	Brown shaly sandstone.
829.3 - 831.0	Brown slightly shaly sandstone.
831.0 - 832.0	Brown sandstone.
832.0 - 833.1	Brown shaly sandstone.
833.1 - 834.0	Gray sandy shale.

Oilfield Research Laboratories

RESULTS OF SATURATION & PERMEABILITY TESTS

TABLE 1

Company Beckett Oil Company Lease Teats Well No. 10

Sample No.	Depth, Feet	Porosity Percent	Percent Saturation			Oil Content Bbls. / A Ft.	Perm., Mill.
			Oil	Water	Total		
1	825.5	18.1	53	7	60	744	3.4
2	826.5	20.2	63	4	67	987	42.
3	827.5	20.1	58	6	64	904	41.
4	828.5	12.1	33	50	83	310	Imp.
5	829.5	14.0	30	42	72	326	6.8
6	830.5	16.3	41	28	69	519	7.4
7	831.5	17.5	67	14	81	910	37.
8	832.5	17.3	60	16	76	805	Imp.