

OILFIELD RESEARCH LABORATORIES

536 NORTH HIGHLAND - CHANUTE, KANSAS 66720 - PHONE (316) 431-2650

March 27, 1980

Beckett Oil Company
620 E. Carpenter
Iola, Kansas 66749

Gentlemen:


Attached hereto are the results of tests run on the rotary core taken from the Teats Lease, Well No. 11, Allen County, Kansas, and submitted to our laboratory on March 21, 1980.

The core was sampled by a representative of Oilfield Research Laboratories after it was received in the laboratory.

Your business is greatly appreciated.

Very truly yours,

OILFIELD RESEARCH LABORATORIES


Sanford A. Michel

SAM/kas
5 c to Iola, Kansas

Oilfield Research Laboratories

RESULTS OF SATURATION & PERMEABILITY TESTS

TABLE 1

Company Beckett Oil Company Lease Teats Well No. 11

Sample No.	Depth, Feet	Porosity Percent	Percent Saturation			Oil Content Bbls. / A Ft.	Perm., Mill.
			Oil	Water	Total		
1	829.5	20.9	53	13	66	859	110.
2	830.5	21.3	49	16	65	810	195.
3	831.5	15.1	61	26	87	715	11.
4	832.6	16.7	64	16	80	829	Imp.

OILFIELD RESEARCH LABORATORIES

LOG

Name Beckett Oil Company Lease Teats Well No. 11

<u>Depth Interval, Feet</u>	<u>Description</u>
829.0 - 830.9	SQUIRREL SAND Dark brown sandstone.
830.9 - 832.2	Brown laminated sandstone and shale.
832.2 - 833.1	Brown shaly sandstone.
833.1 - 838.0	Brownish gray sandy shale.