

** The person who can be reached by phone regarding my questions concerning this information.

SIDE TWO

OPERATOR Mack C. Colt, Inc.

LEASE Bowen 20A0

ACO-1 WELL HISTORY
SEC. 35 TWP. 24 RGE. 20E

FILL IN WELL LOG AS REQUIRED:

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.			SHOW GEOLOGICAL MARKERS LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.	
FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Soil and clay	0	5		
Lime	5	7		
Shale	7	8		
Lime	8	19		
Shale	19	33		
Lime, sdy	33	45		
Shale	45	57		
Lime	57	59		
Shale	59	115		
Lime	115	187		
Shale	187	193		
Lime	193	215		
Shale	215	219		
Lime	219	235		
Shale	235	238		
Lime	238	250		
Shale	250	410		
Lime	410	428		
Shale	428	436		
Lime	436	445		
Shale	445	518		
Lime	518	545		
Shale	545	585		
Lime	585	601		
Shale	601	608		
Lime	608	612	Fort Scott LS	608-612
Shale	612	685		
Lime	685	687		
Shale	687	810		
Siltstone	810	816		
Shale	816	820		
Sand	820	821.8		
Shale	821.8	822.3		
Sand	822.3	825.6		
Coal	825.6	826		
Clay	826	830		
Shale	830	842		
T.D.	842'			

Report of all strings set — surface, intermediate, production, etc. CASING RECORD New or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface pipe	9 5/8"	6 5/8"	28#	38.8	Neat	13	-----
Production	6"	2 3/8"	4.6#	838'	50-50 pozmix	143	----

LINER RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
----------	-------------	--------------	---------------	-------------	----------------

TUBING RECORD

Size	Setting depth	Packer set at			
------	---------------	---------------	--	--	--

1

14 gr. glass

818 - 824

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Frac w/2500# frac sand	818 - 824

Date of first production	Producing method (flowing, pumping, gas lift, etc.)	Gravity
1-18-84	pumping	21

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	2 bbls.	----- MCF	%	----- bbls.

Disposition of gas (vented, used on lease or sold)

used on lease

Perforations

818 - 824

284348