

BECKER-REED OIL & GAS COMPANY.

NORTH WEST DOME - Bill Myers - Well No. 1.

Barker Bros. - Contractors.

nw 1/4 sec 16 24-20 allen county

Feet. Formation - Bottom Depth.

4	Soil	4
3	Clay	7
27	Lime	34
50	Shale -Dark	84
20	Shale - Light	104
23	Shale - Dark	127
68	Lime	195
5	Shale - Blue -Water	200
3	Lime	203
3	Shale - Dark	206
39	Lime	245
2	Shale - Dark	247
8	Lime	255
63	Shale - Dark	318
30	Shale - Light	348
27	Shale - Dark	375
5	Shale - Light	380
3	Lime	383
37	Shale - Light	420
4	Lime	424
11	Shale - P ?	435
5	Shale - Light	440
20	Lime	460
13	Shale - Light	473
17	Gas Sand	490
2	L. Shale	492

pecker set in this time about 455

Spudded in Dec. 30, 1921.
Finished Jan. 5, 1922.

10 Ft. of 8 1/4" pipe set.
398 Ft. of 6 1/4" pipe set.

488 Ft. of 2" Tubing.

*474
450
42*

Becker-Reed Oil and Gas Company.

North West 1/4 - Bill Myers - Well No. 1.

Parker Bros. - Contractors.

NW 1/4 Sec. 16, 24-20 Allen County, Kansas.

4	Soil	4
3	Clay	7
27	Lime	34
50	Shale - Dark	34
20	Shale - Light	104
23	Shale - Dark	127
68	Lime	195
5	Shale - Blue - Water	200
3	Lime	203
3	Shale - Dark	206
39	Lime	245
2	Shale - Dark	247
8	Lime	255
63	Shale - Dark	318
30	Shale - Light	348
27	Shale - Dark	375
5	Shale - Light	380
3	Lime	383
37	Shale - Light	420
4	Lime	424
11	Shale	435
5	Shale - Light	440
20	Lime	450
13	Shale - Light	473
17	Gas sand	490
2	Light Shale	492

Packer set in this line
about 455

Spudded in Dec. 30, 1921.

Finished Jan. 5, 1922.

10 Ft. of 8 1/2" pipe set.
392 Ft. of 6 1/2" pipe set.

488 Ft. of 2" tubing.