

BECKER-Reed OIL & GAS COMPANY.

Flack Farm - Well No. 1. - Started Febr. 16, 1922.

Finished Febr. 20, 1922.

E ½ N E ¼ Sec 16 - 24-20 Allen County Kan

Feet. Formation - Bottom Depth.

3	Soil	3
2	Clay	5
27	Lime	32
40	D. Shale	72
25	L. Shale	97
27	D. Shale	124
68	Lime	192
3	D. Shale	195
3	Lime	198
4	D. Shale	202
18	Lime	220
5	B. Shale- Water-	225
10	Lime	235
5	B. Shale	240
5	Lime	245
20	L. Shale	265
50	D. Shale	315
20	L. Shale	335
45	D. Shale	380
3	Lime	383
23	L. Shale	406
22	D. Shale	428
2	Lime	430
13	L. Shale	443
12	Lime	455 - packer set here
5	D. Shale	460
18	L. Shale	478
19½	Gas Sand	497½

7 Ft. of 8½" pipe set.

386 Ft. of 6½" pipe set.

494 Ft. of 2" Tubing set.

Packer 4 - Set at 450 Ft.

Becker-Reed Oil and Gas Company.
 Flack Farm - Well No. 1. Started Febr. 16, 1922
 E 1/2 NE 1/4 Section 16 - 24-20 Allen County, Kansas.
 Finished Febr. 20, 1922

3	Soil	3
2	Clay	5
27	Lime	32
40	D. Shale	72
25	L. Shale	97
27	D. Shale	124
68	Lime	192
3	D. Shale	195
3	Lime	198
4	D. Shale	202
18	Lime	220
5	B. Shale- Water-	225
10	Lime	235
5	B. Shale	240
5	Lime	245
20	Light Shale	265
50	D. Shale	315
20	L. Shale	335
45	D. Shale	380
3	Lime	383
23	L. Shale	406
22	D. Shale	428
2	Lime	430
13	L. Shale	443
12	Lime (packer set here)	455
5	D. Shale	460
18	L. Shale	478
19 1/2	Gas Sand	497 1/2

7 Ft. of 8 1/2" pipe set.
 386 Ft. of 6 1/2" pipe set.
 494 Ft. of 2" Tubing set.
 Packer 4 - set at 455 Ft.