

PORE

STEWART-HONNEUS 54AD

1043.3

671
+ 372.3

8-671 sh lt gry slicken

674 ss, vy fn gr ^{gry} w/ scat sid fr 672-673

678.7 sh. lt gry w/ ^{abund} scat sid

679.0 ss vtr, vy fn gr good sat

679.6 siltst wh w/ lt sat

19-684.5 ss, vy fn gr, good sat, vy slty fr. 681.5-681.9 (lt sat)

686.0 siltst, lt gry, w/ lt gry sh intert no sat

5-690.9 ss vtr, sh uniform gr, good sat

691.65 lbd w/ live & dead oil sat

693.1 siltst wh & vy fn gr ss, vy lt sat, sid zn fr. 692.7-693.1

694.2 siltst, wh intert & interb w/ sh lt gr.

695.2 sh. med gry

697.5 siltst, wh & sh lt gry 70:30

698.2 ss, vy fn gr spotted fair sat w/ 1/2 - 1/4" wavy wh siltst.

679'

701.4 siltst, sh, ss vy fn gr thinly intert & intert, no sat

680'

702.0 siltst, wh

681'

702.1 Coal

682'

704 Underlay med gry, vy slty crenulated

683'

705.4 sh med - dk gry w/ abund intert w/ siltst.

12
SMOTS

684'

713.9 sh blk, some slicken, 1/8" coal @ base

719.3 sh gry, ^{stly} slty, sid in middle part.

BURBANK 686'

SPLS

7-721 lbit

687'

688'

728 sh med gry

689'

731 Coal

690'

No Depth corrections

691'

cored interval : 668 - 731

No. of boxes : 18

shelf loc : NB-D_{6,7}