

- 73-675 Sh, med gry, no bedding & turned up by organisms
- 677.5 Sh, " "
- 679 Sh, mottled gry & blk, no bedding
- 682.2 Sh, med gry w/abund wh siltst interl & scat sid
- 683.4 siltst, wh w/ good oil sat fn gr ss fr. 682.8-682.9 and 683.3-683.4
- 685.5 ss, vitr, fn gr. w/50% wh siltst ptings, ss w/ good sat
- 686.5 siltst wh, thruwy interb & intert w/ sh med gry
- 689.2 ss, fn, evengr, good sat
- 690.1 siltst, wh, w/ X strat sh lam
- 694.4 ss fn even gr, good sat
- 695.2 ss " " " " " w/ 1/32-1" wh siltst interbeds
- 697 ss " " " " " w/ 50% X strat wh siltst
- 697.9 siltst, wh, w/ X strat sh, gry
- 698.9 ss, fn gr, good sat
- 700 siltst, wh X strat & interb & intert w/ sh gry
- 705.5 sh, med gry, interb & intert w/ siltst med gry, locality sid
- 705.6 Coal
- 710 sh, med gry, abund burrowed
- 711.8 lbid w/ abund intert wh siltst
- 718 sh, dk gry → dk, carb, mod siltst, wh in bot. 5
- 718.2 Coal
- 721 Clay sh, lt gry, slicken, sl. calc sl, slty
- 723.7 siltst lt gry w/ med <sup>gry</sup> sh intert, 1s fr. 722.4-722.6, w/ sid in bot. 3'
- 730 sh, med gry sid
- 733 sh, blk, slicken
- 733.7 Coal
- 734.5 sh dk gry
- 735.3 Coal

NO GAMMA  
CORRECTION

~~698~~  
 683  
 684  
 685  
 686  
 687  
 688  
 689  
 690  
 690  
 691  
 693  
 694  
 695  
 698  
 697  
 698

- 736.7 clay sh lt gry, abunt plant fossils, silty  
739.2 sh blk slicked  
742.6 sh lt gry w/scat wh siltst lam  
746.4 siltst wh w/ 25% sh, med gry interl.  
749.1 sh, med gry w/ 10% interl wh siltst

Cored Interval : 673 - 749.1

No. of boxes : 21

shelf loc. : NB-DS, 6