

KANSAS

WELL COMPLETION REPORT AND DRILLER'S LOG

State Geological Survey
WICHITA BRANCH
Renewed 2/26/82

And

S. 27 T. 24 R. 22 E

Loc. NE 1/4

County Bourbon

API No. 15 — 011 — 21087
County Number

Operator
Reese Exploration, Inc.

Address
P. O. Box 11598, K.C. Mo. 64138


Well No. 1-81 Lease Name Mix

Footage Location
50 feet from (N) line 50 feet from (E) line

Principal Contractor Geologist
Michael Drilling, Inc.

Spud Date 3-24-81 Date Completed 3-25-81 Total Depth 542 P.B.T.D.

Directional Deviation Oil and/or Gas Purchaser
Maclaskey



Released
11 MAR 1983
Date: FROM CONFIDENTIAL

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	8-7/8	6-1/4	17#	40	Portland	4	none
2"	5-1/4	2-3/8	4#	521	"	90	2% Gel

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
none					

Size	Setting depth	Packer set at
none		

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Frac - Gelled Water - 60 sacks sand	

INITIAL PRODUCTION

Date of first production May 1981	Producing method (flowing, pumping, gas lift, etc.) Pumping
RATE OF PRODUCTION PER 24 HOURS	Oil 1 bbls. Gas 0 MCF Water 0 bbls. Gas-oil ratio CFPB
Disposition of gas (vented, used on lease or sold)	Producing interval (s)

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator
Reese Exploration, Inc.

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:
Oil

Well No. 1-81
Lease Name Mix

S 27 T 24 R 22 ^E
XX

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Soil and clay	0	3		
lime	3	41		
shale	41	50		
s. lime	50	52		
shale	52	58		
lime	58	76		
shale	76	81		
lime	81	84		
shale	84	97		
lime	97	111		
shale	111	276		
lime	276	282		
shale	282	368		
lime	368	386		
shale	386	389		
lime	389	395		
shale	395	439		
lime	439	453		
shale	453	462		
lime	462	466		
sandy shale	466	476		
sand oil	476	490		
shale	490	542		

RELEASED
MAR 31 1983
FROM CONFIDENTIAL

PRODUCTION
JUN 5 1981
RECEIVED

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	<i>P. E. E. E.</i> Signature
	Bookkeeper
	Title
	June 5, 1981
	Date

853358