

KANSAS



State Geological Survey
WICHITA BRANCH

and

WELL COMPLETION REPORT AND
DRILLER'S LOG

S. 27 T. 24 R. 22 E
NE 1/4

API No. 15 — 011 — 21136
County Number

County Bourbon

Operator
Reese Exploration, Inc.

RELEASED
Date: JUN 7 1982
FROM CONFIDENTIAL

640 Acres
N

Address
P.O. Box 11598 K.C. Mo. 64138


Well No. 18-81
Lease Name Mix

Footage Location
380 feet from (N) (S) line 1900 feet from (E) (W) line

Principal Contractor
Michael Drilling, Inc.

Spud Date 4-14-81
Date Completed 4-15-81
Total Depth 522
P.B.T.D.

Directional Deviation
Oil and/or Gas Purchaser
Maclaskey



Locate well correctly

Elev.: Gr.

DF KB

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	8-7/8	6-1/4	17#	40	Portland	4	none
2"	5-1/4	2-3/8	4#	506	"	90	2% Gel

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
none					

Size	Setting depth	Packer set at
none		

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Frac - Gelled Water - 60 sacks sand	

INITIAL PRODUCTION

Date of first production May 1981	Producing method (flowing, pumping, gas lift, etc.) Pumping
RATE OF PRODUCTION PER 24 HOURS	Oil 1 bbls. Gas 0 MCF Water 0 bbls. Gas-oil ratio CFPB
Disposition of gas (vented, used on lease or sold)	Producing interval(s)

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be trans-
mitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation
Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note
Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:
Oil

Operator
Reese Exploration, Inc.

Well No. 18-81 Lease Name Mix

S 27 T 24 R 22 E
~~XX~~

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Soil and clay	0	10		
lime	10	21		
shale	21	26		
lime	26	28		
shale	28	37		
lime	37	63		
shale	63	68		
lime	68	72		
shale	72	82		
lime	82	96		
shale	96	257		
lime	257	265		
shale	265	347		
lime	347	366		
shale	366	368		
lime	368	374		
shale	374	418		
lime	418	430		
shale	430	443		
lime	443	447		
shale	447	454		
sandy shale	454	459		
sand-oil	459	467		
shale	467	522		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	<i>Dotty Erickson</i>
	Signature
	Bookkeeper
	Title
	June 5, 1981
	Date

436447