

15-011-20498

IMPORTANT
Kans. Geo. Survey request
samples on this well.

State Geological Survey
WICHITA BRANCH
KANSAS DRILLERS LOG

S. 3 T. 24 R. 23 E
W
Loc. SW SW SW
County Bourbon

API No. 15 — 011 — 20,498
County Number

Operator
Gator Drilling Fund 1977-2 Ltd.

Address
P. O. Box 1628 Lake Worth, Fl.


Well No. #4 Lease Name
McCliney

Footage Location
330 feet from (S) line 165 feet from (W) line SW/4

Principal Contractor Geologist
Nance Drilling Co Jay Robertson

Spud Date Total Depth P.B.T.D.
11-17-78 685

Date Completed Oil Purchaser
11-21-78



Elev.: Gr.
DF KB

CASING RECORD

Report of all strings set— surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Overburden	9"	7	20	52	PORTLAND	10	3% CAI
Production	6 1/4"	2 7/8	4.9	350	circulated		

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			1		300-310

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
140 BBIs water salt & 4000 lbs SAND	300-310

INITIAL PRODUCTION

Date of first production 8-1-79	Producing method (flowing, pumping, gas lift, etc.) PUMPING
RATE OF PRODUCTION PER 24 HOURS Oil 1/2 bbls. Gas — MCF Water 1/2 bbls.	Gas-oil ratio — CFPB
Disposition of gas (vented, used on lease or sold)	Producing interval (s) 300-310

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Gator Drilling Fund 1977-2 Ltd DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Well No. 4 Lease Name McLiney

S T R E W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Overburden	0	16		
Gray Shale	16	58		
Pink Shale	58	62		
Dark Gray Shale	62	78		
Lime	78	84		
Dark Gray Shale	84	89		
Lime	89	97		
Dark Gray Shale	97	109		
Pink Shale	109	112		
Dark Gray Shale	112	178		
Lime	178	197		
Black Shale	197	201		
Lime	201	207		
Black Shale	207	209		
Dark Gray Shale	209	249		
Lime	249	267		
Dark Gray Shale	267	272		
Lime	272	278		
Dark Gray Shale.	278	289		
Gray Sand Show of oil	289	346	<i>squirrel</i>	
Dark Gray Shale	346	397		
Lime	397	398		
Dark Gray Shale	398	400		
Black Shale	400	410		
Med. Dark Gray Shale & Sand	410	430		
Dark Gray Shale & Lime Streaks	430	450		
Black Shale	450	470		
Dark Gray Shale	470	560		
Dark Gray & Black Shale	560	644		
Chert	644	648		
		648		
Brown Lime	648	685	Top Of Miss.	
		685	T.D.	

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received _____

Gator Oil Company
By L.W.A. Halter V.P.
Signature
General Partner
Title
Date _____

536652