

Company Smith-Crowder

Farm L.G. Kepley

No. 1

Sec. 34 T. 24 R. 23E

Loc. NEc NE 1/4

County Bourbon

Total Depth

Comm. 1-3-38

Comp.


Shot or Treated

Contractor

Issued

Casing

20 in.	10 in
15 1/2	8 1/4
12 1/2	6 5/8
13 3/8	5 3/16



Elevation

Production

Figures Indicate Bottom of Formation

5	Soil	5	
23	Shale	28	
2	Lime	30	
3	Shale White	33	
9	Lime	42	
13	Shale Sandy	55	
17	Shale Blue	82	
13	Oil Sand	95	oil
35	Shale Blue Muddy	130	
20	Lime	150	
3	Shale Blk	153	
6	Lime	159	162 reduced hole
26	Shale Dark	185	wtr
10	Slate Blk	195	
13	Shale Light	208	
14	Lime	222	
6	Slate Blk	228	} gas Oswego
5	Lime	233	
17	Shale Light	250	
15	Shale Dark	265	
10	Shale Light	275	
22	Shale Gray	297	
2	Lime	299	
5	Slate Blk	304	
2	Lime Shells	306	
24	Shale Blk	330	
7	Shale Light	337	
3	Lime	340	packer set 340
7	Shale Blk & Sand	347	gas 337 bolt 3' 6" blow
8	Shale Light	355	packer
2	Shale Sandy	357	
53	Sand	410	
12	Shale Sandy	422	
13	Shale White	435	
15	Shale & Coal	450	
6	Shale White	456	
4	Shale Blk	460	
20	Shale White	480	
5	Shale Blk	485	
28	Shale White	513	
24	Shale Sand	539	Bottom

Gift From
Claude Crowder