

KANSAS DRILLERS LOG

API No. 15 — 011 — 20-315
County Number

Operator

Gator Oil Company

Address

P. O. Box 1628 Lake Worth, Florida 33460

Well No.

1

Lease Name

R. Russell

Footage Location

660 feet from (N) (S) line 660

feet from (E) (W) line SW 1/4

Principal Contractor

Nance Well Drilling

Geologist

Jay Robertson

Spud Date

1/2/78

Total Depth

625 ft.

P.S.T.D.

Date Completed

1/3/78


Oil Purchaser

S. 32 T. 24S R. 23 E

Loc. Center SE SW

County Bourbon

640 Acres
N



Locate well correctly

Elev.: Gr.

Dt.

KB

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs./ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	9"	7"	20 lb.	28'		5	
Production	6 1/2	2 7/8	4.7	625'	circulated		

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			1	20 gram	600-14

TUBING RECORD

Size	Setting depth	Pecker set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
300 gallon acid pumped	600-14

INITIAL PRODUCTION

Date of first production 7-18-78	Producing method (flowing, pumping, gas lift, etc.) Flowing
RATE OF PRODUCTION PER 24 HOURS	Oil Gas Water Gas-oil ratio
Disposition of gas (vented, used on lease or sold) Shut-in	Producing interval(s) 600-14

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Gator Oil Company		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, FWDW, ETC.:
Well No. 1	Lessee Name R. Russell	gas
32 T24 R 23 E		


WELL LOG

Show all important zones of porosity and contents thereof; record intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Overburden	0	4		
Grey Shale	4	138		
rown Lime (show of oil)	138	152		
Black Shale	152	155		
ark Grey Shale	155	190		
Light Grey Shale	190	205		
Brown Lime	205	223		
Black Shale	223	227		
Brown Lime	227	232		
Light Grey Shale	232	236		
Black Shale	236	238		
edium Grey Shale	238	248		
and (show of oil)	248	249		
Dark Sandy Shale	249	280		
Grey Shale	280	340		
Grey Lime	340	342		
Grey Shale	342	425		
Grey Sandy Shale (show of gas)	425	445		
Dark Grey Shale	445	460		
Grey Sand	460	472		
Grey Shale	472	510		
Dark Grey Sand (show of oil)	510	525		
Dark Shale	525	580		
Chat	580	625		
D.	625			

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	 Signature Vice President Title Date
---------------	--

0699ES