


KANSAS DRILLERS LOG

State Geological Survey
WICHITA, BRANCHAPI No. 15 — 011 — 20249
County NumberS. 6 T. 24 R. 24 E
Loc. 890'S 271'W, NE/4, NW/4
County Bourbon

Operator AMM, Inc. % D. R. McCord		
Address Kemna KoA, Route 3, Lot E, Fort Scott, Kansas 66701		
Well No. AM-9	Lease Name Feagin's	
Footage Location 890' feet from (N) ~~1st~~ line 271' feet from Final Resurvey		
Principal Contractor M & M Drilling		Geologist ---
Spud Date July 23, 1976	Total Depth 175'	P.B.T.D. 173'
Date Completed July 23, 1976	Oil Purchaser -	

Elev.: Gr. +850
DF KB

CASING RECORD

Report of all strings set— surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs./ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	7 1/2"	6 5/8	13	23'	Portland	1	none
Oil String	4 3/4"	2"	3.75	170'	Portland	20	none

LINER RECORD

PERFORATION RECORD

Top, ft. -	Bottom, ft. -	Sacks cement -	Shots per ft. 1	Size & type Jet	Depth interval 144'-150'
TUBING RECORD					
Size	Setting depth	Packer set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Fracture: 60 bbls water gel, 1.5 sacks sand, 30 gallons HCl	144'-150'

INITIAL PRODUCTION

Date of first production August 22, 1976		Producing method (flowing, pumping, gas lift, etc.) pumping			
RATE OF PRODUCTION PER 24 HOURS	Oil 0.5 bbls.	Gas .001 MCF	Water 0.2 bbls.	Gas-oil ratio 2 CFPB	
Disposition of gas (vented, used on lease or sold) vented			Producing interval (s) 144-150		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator	AMM, Inc.	66701
% D. R. McCord, Route 3, Kemna KOA, Lot E, Ft. Scott, Ks.		

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

Lease Name

Feagin's

Oil

S 6 T 24 R 24 E W

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Limestone	27'	52'	Pawnee	
Limestone	96'	112'	Upper Oswego	
Limestone	118'	122'	Lower Oswego	
Shale	122'	131'	Mulkey Shale	
Sandy Shale	131'	135'	Upper Squirrel	
Oil Sand	135'	147'	Lower Squirrel	
USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received _____

D. R. McCord

Signature

Vice-President

Title

October 19, 1976

Date _____

53651