

KANSAS DRILLERS LOG

S. 6 T. 24 R. 24 E
 W
 Loc. 100' FNL & 60' FWL NW 1/4
 of the SW/4 of the NE/4
 County Bourbon

API No. 15 — 011 — 20,480
 County Number

Operator
AMM, Inc.

Address
Route #2, Box 46-A Mapleton, Kansas 66754

Well No. #F-17 Lease Name R. & V. Feagins


Footage Location
100' feet from (N) ~~X~~ line 60' feet from (W) ~~X~~ line

Principal Contractor Van Michael Geologist -

Spud Date 9/23/78 Total Depth 154 P.B.T.D. 151

Date Completed 9/23/78 Oil Purchaser Maclaskey

*State Geological Survey
 WICHITA BRANCH*



Elev.: Gr. +854
 DF - KB ---

CASING RECORD

Report of all strings set— surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	8 1/2"	6 5/8"	10	18	Portland	2	None
Production	5 1/4"	2 3/8"	4.3	142'	Portland	10	None

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
-	-	-	-	-	-
TUBING RECORD			open hole	packer	139-151
Size	Setting depth	Packer set at			
1"	141	S. N. 141			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Fraced Oil 17 bbls	141 - T.D.

INITIAL PRODUCTION

Date of first production 9/28 Producing method (flowing, pumping, gas lift, etc.) buildup

RATE OF PRODUCTION PER 24 HOURS
 Oil 0.5 bbls. Gas - MCF Water 0 bbls. Gas-oil ratio - CFPB

Disposition of gas (vented, used on lease or sold) vented Producing interval(s) open 141 - 151

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator **AMM, INC.** DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Well No. **F-17** Lease Name **R & V Feagins** Oil


S 6 T 24 R 24 ^E_{MX}

WELL LOG
 Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries. SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Soil	0	11		
Shale	11	21		
Coal	21	23		
Shale	23	29		
Limestone	29	53		
Shale	53	92		
Limestone	92	114		
Shale	114	122		
Limestone	122	124		
Shale	124	130		
Sand & Shale	130	140		
Sand	140	151		
P.B. 151'				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received _____


 Signature **D. R. McCord**
 Title **Vice-President**
 Date **June 10, 1979**

644985