

CASING RECORD

Well Log Bur. Ks Geo Soc.
LOCATION Southwest cor SW 1/4 SE 1/4

SEC 25 T 24 R 6 E

10"
20" 8 1-4
15 1-2 6 5-8
12 1-2 5 3-16

FARM Dailey

NO. 1

COUNTY

Butler

COMPANY Manhattan Oil Company.

CONTRACTOR

COMMENCED

COMPLETED

TOTAL DEPTH 2761'.

SHOT

QUARTS BETWEEN

CORRESPONDENCE REGARDING THIS WELL SHOULD BE REFERRED TO

Manhattan Oil Co.,

Eureka, Kansas.

ELEVATION 1381

FIGURES INDICATE BOTTOM OF FORMATIONS.

INITIAL PRODUCTION D. & A.

REMARKS

Formation	Depth
lime	50
sand HFW	60
lime	70
shale	85
shale & lime	370
shale	400
lime	450
shale & lime	535
shale	565
lime	575
shale	625
sandy shale	640
shale	670
sand (8 B.W.)	690
shale	715
sand (HFW 12 $\frac{1}{2}$ " set)	730
shale	785
shale & lime	935
lime	1020
shale	1065
shale & lime	1135
sandy shale	1175
shale	1215
lime	1260
shale	1320
lime	1330
shale	1340
lime	1385
shale	1435
lime	1515
shale	1555
sand (4 BW 1595')	1585
(10" csg. set)	
shale	1705
lime	1710
shale	1780
lime (3 B. W.)	1950
shale 2125 HFW	2080
lime	2225
shale (8" csg. 6-15-26)	2380
lime	2500
shale (Set 6" at 2555')	2575
About 400' of water in hole)	
(6-24-26.	
Drilling ahead 6-25-26.	
shale	2655
sandy shale	2662
shale	2670
shale	2712
sand HFW	2744
shale	2755
lime	2761
Total Depth	2761'.